

Work Write-Up and Bid Document

Stephen Batt

471681 HWY 101

sallisaw, OK

74955-

(918) 776-0880

Contractor Name

Contractor Signature

Bid Due Date:

Trade	Area	Description	Comments	Manual Spec	Quantity	Enter Bid
-------	------	-------------	----------	-------------	----------	-----------

Carpentry

EXTERIOR

1		Storm Door/Vinyl Clad/Replace storm/screen door with new self storing storm door/Vinyl Clad/Use Larson model 298-SS or written approved equal.	replace storm doors	8.B	3 EA	<input type="text"/>
---	--	--	---------------------	-----	------	----------------------

Electrical

HALLWAY #1

2		Smoke Detector/Battery Operated/Install new smoke detector, battery operated (10 year lithium battery). All bedrooms and hallways adjacent to bedrooms. Use Firex #4015 or written approved equal.	replace smoke alarms	13.D.11	2 EA	<input type="text"/>
---	--	--	----------------------	---------	------	----------------------

HVAC

HALLWAY #1

Thursday, July 30, 2015

471681 HWY 101

sallisaw, OK

Page 1 of 2

Trade	Area	Description	Comments	Manual Spec	Quantity	Enter Bid
-------	------	-------------	----------	-------------	----------	-----------

HVAC

HALLWAY #1

3		Central Air (13 SEER) & Heat/1,001 to 1,600sf/Install central air (13 SEER) and heat (gas-80% AFUE)/Complete system/Building sizes between 1,001 and 1,600sf.	replace with 3 ton unit, to include lineset, filter and filter grill, and stat.	12	1280 SF	<input type="text"/>
---	--	---	---	----	---------	----------------------

Roofing

EXTERIOR

4		Roof/shingles/Install. Install new 30 year architectural shingles as per manufacturer's recommendations.	remove and replace shingles, drip edge, roof jacks, felt and flashing.	7.A.	26 S	<input type="text"/>
---	--	--	--	------	------	----------------------

TOTAL