

# Work Write-Up and Bid Document

**Shop / Yard Fence Fence**

1300 Nola St

Tahlequah, OK

74464-

(918) 871-9169

Contractor Name \_\_\_\_\_

Contractor Signature \_\_\_\_\_

Bid Due Date: \_\_\_\_\_

Trade	Area	Description	Comments	Manual Spec	Quantity	Enter Bid
-------	------	-------------	----------	-------------	----------	-----------

*Site Work*

**EXTERIOR**

1		Fence/Chain link/ 9 gauge mesh 6 ft/ Install 6 ft. high chain link fence with 3 strands of barbed wire at top.	Install 6 Ft. chain link To include 3" sch. 40 corner post, 2" sch, 40 line post, 1/58" CQ 20 Toprail.	2.m	850 LF	<input style="width: 100%;" type="text"/>
---	--	--	--	-----	--------	---

2		Gate/chain Link/6ft. Install 6ft High. Chain link gate.	Install two (2) 20' Double Drive Gates w/Adjustable truss rod supports & 1 5/8 welded frame w/ 3 strands barb wire on top.	2.m	2 EA	<input style="width: 100%;" type="text"/>
---	--	---	--	-----	------	---

TOTAL

**Bid must meet or exceed the following minimum specifications:**

- 9 Gauge Mesh
- Corner Post – 3” Sch. 40
- Line Post – 2” Sch. 40 with 3Strands Barb Wire
- Top Rail – 1-5/8” CQ20
- Drive Gate – Adjustable Truss Rod Support, 1-5/8” welded frame with 3 strand barb wire