

# WorkWrite-Up and Bid Document

**Eddie Ross**  
18107 Samuel Street  
Tahlequah, OK  
74464-  
(918) 316-2048

Contractor Name \_\_\_\_\_

Contractor Signature \_\_\_\_\_

**Bid Due Date:** \_\_\_\_\_

Trade	Area	Description	Comments	Manual Spec	Quantity	Enter Bid
<i>Carpentry</i>						
<b>1</b>	<b>KITCHEN</b>	Fire Extinguisher/Install. Install new fire extinguisher.	Install fire extinguisher	10.G	1 EA	<input type="text"/>
<i>Electrical</i>						
<b>2</b>	<b>INTERIOR</b>	Smoke Detector/Battery Operated/Install new smoke detector, battery operated (10 year lithium battery). All bedrooms and hallways adjacent to bedrooms. Use Firex #4015 or written approved equal.	Install one in hallway. And one in each bedroom	13.D.11	4 EA	<input type="text"/>

*HVAC*

**HVAC**

<i>Trade</i>	<i>Area</i>	<i>Description</i>	<i>Comments</i>	<i>Manual Spec</i>	<i>Quantity</i>	<i>Enter Bid</i>
<i>HVAC</i>						
	<b>HVAC</b>					
<b>3</b>		Central Air (13 SEER) & Heat/1,001 to 1,600sf/Install central air (13 SEER) and heat (gas-80% AFUE)/Complete system/Building sizes between 1,001sf and 1,600sf.	Remove and replace 3 ton hvac system. To include thermostat, stat wire, furnace, coil, condenser, filter and grill, and flu pipe	12	1500 SF	<input type="text"/>
<i>Plumbing</i>						
	<b>INTERIOR</b>					
<b>4</b>		Water Heater/Gas/40 Gallon/Install new 40 gal. gas water heater. Work shall include elevating to 18" (if in garage), replacement of TPR, all combustion air and gas & electrical hook-ups for code legal installation.	Remove and replace hwt. Include flu pipe	11.A	1 EA	<input type="text"/>
<i>Roofing</i>						
	<b>ROOF</b>					
<b>5</b>		Shingles/Install 30 year shingle.(architectural shingle)	Remove and replace shingles, tar paper, jacks, drip edge, ect	s.5	26 sq	<input type="text"/>
						<b>TOTAL</b> <input type="text"/>