

WorkWrite-Up and Bid Document/By Trade

Lorene Foreman

49819 S. 624 Road Colcord, OK 7-4338
(479) 233-0898

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: Rehabilitation

Bid Due Date:

| <i>Trade</i> | <i>Work Description / Comments</i> | <i>Gen. Spec.</i> | <i>Qty Unit</i> | <i>Item Bid</i> |
|--------------------------|---|-------------------|-----------------|---|
| <u>Carpentry</u> | | | | |
| 1 | <i>Area:</i> KITCHEN Fire Extinguisher/Install. Install new fire extinguisher. | Div.# 10.G | 1 Ea | <input style="width: 80px; height: 40px;" type="text"/> |
| <u>Electrical</u> | | | | |
| 2 | <i>Area:</i> EXTERIOR Smoke Detector/Battery Operated/Install new smoke detector, battery operated (10 year lithium battery). All bedrooms and hallways adjacent to bedrooms. Use Firex #4015 or written approved equal. | Div.# 13.D. 11 | 5 Ea | <input style="width: 80px; height: 40px;" type="text"/> |
| <u>HVAC</u> | | | | |
| 3 | <i>Area:</i> EXTERIOR HVAC Equipment/Central/Cooling/ Heating/3 TON/13 SEER. Replace existing HVAC equipment (13 SEER). INSIDE FURNACE AND OUTSIDE EQUIPMENT/INCLUDING AIR HANDLER, COPPER LINES, CONDENSOR COILS, EVAP. COILS. AND COMPRESSOR. Propane unit. | Div.# 12 | 1 Ea | <input style="width: 80px; height: 40px;" type="text"/> |

Roofing

| <i>Trade</i> | <i>Work Description / Comments</i> | <i>Gen. Spec.</i> | <i>Qty Unit</i> | <i>Item Bid</i> |
|----------------|---|-------------------|-----------------|----------------------|
| Roofing | | | | |
| 4 | Area: EXTERIOR | <i>Div.# 7.A.</i> | 26 Sq | <input type="text"/> |
| | Roofing/Heritage/30 Year Warranty. Install fiberglass shingles/Minimum 30 year warranty/Use Marlarky/Tamko or written approved equal. | | | |
| | Remove and replace shingles. Replace any deteriorated decking. | | | |

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.

Total:

Lorene Foreman: site directions-From Kansas Ok. Stay on highway 10 north towards Jay at junctions 116 and 10 go north on 10 for 2.2 miles. Turn right on 618 road then right on 494 road. Then turn right on 624 road 1st house on the right.

Phone #479-233-0898