

## **SCOPE OF WORK FOR FLOOR REPLACEMENT**

Repair and replace identified areas of the WSS main kitchen. Contractor shall remove any existing epoxy flooring in the kitchen and prepare area of sealed concrete to be replaced with Poly-Create flooring in accordance with all applicable manufacturers' specifications. This is a large kitchen area and project will likely take 4-5 weeks to complete. Kitchen will be in operation during the entire project. Contractor will be required to secure areas in order to keep dust and debris confined to the work area.

## **WORK WILL INCLUDED**

Work is to include all prep work and removal of old flooring in areas identified. Equipment that can be removed will be prior to work starting by CNE facilities maintenance. Equipment that cannot be moved will be loosened and should be lifted in order to get underneath. Cleanup and disposal of all construction debris and/or old flooring materials is the responsibility of the contractor. All work will be in accordance with safety protocol set forth by Cherokee Nation, OHRC and local codes and procedures to include OSHA.

## **SCHEDULE**

Bid should include reasonable estimate of time the job will take and expected start and finish dates. Identified areas will begin work on Sunday and be completed and read for traffic/usage no later than Noon on Thursday.

## **Qualifications**

Contractors must be trained and certified through Dur-A-Flex and provide references for similar projects.