

WorkWrite-Up and Bid Document/By Trade

Stanley Drywater

903 NW 16th Street Wagoner, OK 7-4955

(918) 485-0431

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: Rehabilitation

Bid Due Date: _____

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<u>Carpentry</u>				
1	<i>Area:</i> KITCHEN Fire Extinguisher/Install. Install new fire extinguisher.	<i>Div.#</i> 10.G	1 Ea	<input style="width: 80px; height: 30px;" type="text"/>
<u>Electrical</u>				
2	<i>Area:</i> INTERIOR Smoke Detector/Battery Operated/Install new smoke detector, battery operated (10 year lithium battery). All bedrooms and hallways adjacent to bedrooms. Use Firex #4015 or written approved equal. Install in kitchen, hallway and all bedrooms.	<i>Div.#</i> 13.D. 11	5 Ea	<input style="width: 80px; height: 30px;" type="text"/>
<u>HVAC</u>				
3	<i>Area:</i> GARAGE HVAC /Central/Cooling & Electric Furnace Heating Upflow 3 TON/13 SEER, Replace existing HVAC Equipment (13 SEER). INSIDE AND OUTSIDE EQUIPMENT/INCLUDING; Disconnect, and all necessary electrical wiring for this installation.	<i>Div.#</i> 12	1 Ea	<input style="width: 80px; height: 30px;" type="text"/>

Plumbing

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
Plumbing				
4	<i>Area:</i> GARAGE	Div.# 11.A	1 Ea	<input type="text"/>
Water Heater/Gas/30 Gallon/Replace. Replace existing gas water heater with new 30 gal. gas water heater. Work shall include elevating to 18" (if in garage), replacement of TPR, all combustion air, gas & electrical hook-ups for code legal installation.				

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.

Total:

Stanley Drywater-site directions, Norwood addition, Wagoner Ok. Take highway 51 to Wagoner turn left on 16 go to NW16thth St to 69.

903 NW 15th St. Wagoner Ok

918-485-0431