



Map data ©2023 Google 2 mi

Tahlequah
Oklahoma 74464

Drive from State Hwy 82, S Blue Top Rd and S 4620 Rd to
Sallisaw

57 min (40.5 mi)

- ↑ 1. Head south on S Muskogee Ave toward W Shawnee St
● Pass by BancFirst (on the right in 0.2 mi) 4.1 mi
- 🔄 2. At the traffic circle, take the 2nd exit onto State Hwy 82 14.2 mi
- ↶ 3. Turn left onto S Blue Top Rd 8.6 mi
- ↑ 4. Continue onto N4600 Rd/Old US Hwy 17 1.3 mi
- ↗ 5. Slight right onto N4610 Rd 3.0 mi
- ↑ 6. Continue onto Dwight Mission Rd/N4590 Rd 0.2 mi
- ↶ 7. Turn left onto Seminole Ave 1.2 mi

↪ 8. Turn right onto S 4620 Rd

6.5 mi

↑ 9. Continue onto N Maple St

1.4 mi

↪ 10. Turn right

⚠ Restricted usage road

📍 Destination will be on the right

22 sec (256 ft)

1401 N Maple St #78

Sallisaw, OK 74955



Housing Authority of the Cherokee Nation
 PO Box 1007,
 Tahlequah, Oklahoma 74465-1007
 918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Structure (Housing Authority of the Cherokee Nation)		Claim #10196, SHIRLEY YOUNG
<input type="checkbox"/> Approved		

ROOFPLAN: Roofplan

Roof	
Roof area: 1,286.40 SF Squares: 12.9 SQ Soffit: 361.48 SF Eaves: 156.00 LF Ridge: 78.00 LF	

1 Tear Off and Haul Away, Shingles	12.86	SQ
2 Ridge Cap Shingles, Fiberglass, High Profile, Designer - Replace	78.00 (85.80)	LF
<input type="checkbox"/> Includes 10% waste on material quantity.		
3 Felt, Synthetic Good - Replace	12.86	SQ
4 Sheathing, Material Only 1/2" OSB	150.00 (157.50)	SF
<input type="checkbox"/> Includes 5% waste on material quantity.		
5 Soffit, Plywood 1/2" - Tear Out	361.48	SF
6 Soffit, Plywood 1/2" - Replace	361.48 (379.55)	SF
<input type="checkbox"/> Includes 5% waste on material quantity.		
7 Fascia, PVC 8" - Tear Out	189.00	LF
8 Fascia, PVC 8" - Replace	189.00 (198.45)	LF
<input type="checkbox"/> Includes 5% waste on material quantity.		
9 Roof Vent, Turbine Medium - Tear Out	1	EA
10 Roof Vent, Static, Box/Turtle, Aluminum - Replace	4	EA
<input type="checkbox"/> Replace 1 and add 3 new Vents		
11 Roof Jack (MH) - Tear Out	3	EA
12 Roof Jack (MH) - Replace	3	EA
13 Soffit - Paint, 1 Coat	722.46	SF
<input type="checkbox"/> 2 coats of paint		
14 Fascia - Paint, 1 Coat	378.00	LF
<input type="checkbox"/> 2 coats of paint		
15 Soffit Vent (LF) - Replace	172.72 (181.36)	LF
<input type="checkbox"/> Includes 5% waste on material quantity.		
16 Drip Edge (Gutter Apron) Aluminum, Pre-Finish Color, 5" - Tear Out	156.00	LF
17 Drip Edge (Gutter Apron) Aluminum, Pre-Finish Color, 5" - Replace	156.00 (163.80)	LF
<input type="checkbox"/> Includes 5% waste on material quantity.		
18 Drip Edge (Rake Only) Aluminum, Pre-Finish Color - Tear Out	33.00	LF
19 Drip Edge (Rake Only) Aluminum, Pre-Finish Color - Replace	33.00 (34.65)	LF
<input type="checkbox"/> Includes 5% waste on material quantity.		
20 Shingles, Laminated/Architectural Good - Replace	12.86 (14.15)	SQ
<input type="checkbox"/> Includes 10% waste on material quantity.		

Total: _____