

HACN HOUSING REHAB SITE DIRECTIONS

Name: Brenda Cunningham

Telephone: (918) 697-3822

Address: 406 East Loy Avenue
Chouteau, OK 74337

County: Mayes **Year Built:** 1986

GPS Coordinates: 36.18457, -95.33683 **Drive Time:** 50 mins



Directions: From Cherokee Nation, Head north on 62 through Tahlequah (changes to 82) stay on 82 into Locust Grove turn left onto hwy 412 go 8 miles turn right onto old hwy 33E (E Main Street) Take a left on S 4th street then left on E Loy Avenue 2nd house on the left

Belle Kingfisher
Cost Estimator/Inspector

11-3-23
Date

Work Write-Up and Bid Document/By Trade

Brenda Cunningham

406 East Loy Avenue Chouteau, OK 7-433
 (918) 697-3822

Contractor Name:

Contractor Signature:

This document must be signed to be a valid bid.

PROJECT TYPE: Emergency Repairs Bid Due Date:

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Carpentry				
1	Area: ROOF Fascia/Replace/1" x 6". Replace Fascia/ Use SmartSide Textured pre-primed Fascia material. Fastnen using recommended nails. Caulk and paint.	Div.#6.P	190 LF	<input type="text"/>
Roofing				
2	Area: ROOF Roofing/Heritage/30 Year Warranty. Install fiberglass shingles/Minimum 30 year warranty/Use Marlarky/Tamko or written approved equal. 30 lb Felt, Painted Style D Drip Edge, Pipe Flashing, Valley Flashing, and Metal Slant Back Vents. (2,360sq) 6 roof jacks, 1 stove stack, 1 Turbine Vent	Div.# 7.A.	24 Sq	<input type="text"/>
3	Area: ROOF Roofing/Strip/Asphalt-Fiberglass. Remove all layers, and haul roofing debris to a Legal Waste Dump for disposal.	Div.# 7.C	24 Sq	<input type="text"/>

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
-------	-----------------------------	------------	----------	----------

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement.

Total: