Statement of Work

Date | 08/29/2023 Client | Gold Strike Casino Job Name | Gold Strike Casino Theater Ladder

Summary

Gold Strike Casino is currently seeking proposals for clearance and re-installation of safety equipment on fixed ladders.

Submittals

- 1. Design approved and stamped by professional engineer registered in Mississippi.
- 2. Complete list of equipment and cost
- 3. Labor cost

Project Scope

This SOW covers the following components, activities, deliverables, and assumptions. Included in this will be hardware procurement, labor to install new equipment, all required cabling, and labeling of all equipment installed.

Contractor Provided Components:

- 1) Equipment and design approved and stamped by professional engineer registered in Mississippi.
- 2) Existing ladder cage to be removed and recycled or legally disposed.
- 3) Provide and install two new OSHA compliant ladder safety cables for existing 27-foot ladders.
- 4) Provide and install one OSHA compliant ladder access gate to restrict ladder access.
- 5) Provide and install two OSHA compliant self-closing gates to the existing ladders.
- 6) Provide and install OSHA compliant safety rail around ladder opening.
- 7) All equipment installation must meet or exceed OSHA requirements for ladder and fall protection.
- 8) Any work involving welding, cutting, or grinding shall require a Hot Work Permit as required by OSHA CFR 29 1910.252. Pre-inspection and post inspection completed with owner representative. All welding shall require a 24-hour fire watch.

Tasks:

1. **Pre-Install** – Contractor will meet with management to develop a project timeline and a systematic install approach.

2. **Installation** – Contractor will install all necessary components to complete the project. This will include.

• Conditions

- Work schedule will be coordinated with management.
- Contractor is responsible for keeping all work areas clean.
- Cabling General Contractor will install, terminate, and test all cabling needed to complete the project.
- Equipment Contractor is responsible for procuring and installing all components needed to complete the project.

3. Testing & Commissioning -

• Provide all instruments for testing and demonstrating in the presence of the management.

• The management reserves the right to make independent tests of all equipment furnished to determine whether the equipment complies with the requirements specified herein and to accept or reject any or all the equipment based on the results thereby obtained.

4. Training –

• Contractor shall provide a minimum of 1 hours of on-site training to management personnel including end users on all system functions.

Deliverables:

(To be provided within 10 days of completion)

- 1. Provide a Warranty Letter to include equipment and installation warranty dates.
- 2. Provide all equipment manuals
- 3. Provide an As-Built document
- 4. Test Reports
- 5. Service Contract (if applicable)

Key Requirements

- An End of Day Update, via email, must be submitted daily to the Gold Strike project manager.
- Contractor has all necessary tools to accomplish tasks associated with the project.
- Contractor understands and agrees to late night and/or overnight working hours if needed.
- No substitutions allowed unless management permission is provided in writing.
- Payment to contractor shall not be authorized until all deliverables are met.