



Map data ©2023 Google 1 mi

Tahlequah  
Oklahoma 74464

**Follow N Grand Ave and State Hwy 82 N to N 4514 Rd/OK-82A**

- 8 min (5.0 mi)
- ↑ 1. Head north on S Muskogee Ave toward E Downing St
- 59 ft
- ↑ 2. Continue straight to stay on S Muskogee Ave
- 0.2 mi
- ↑ 3. Continue onto N Grand Ave/Valley Ave  
Continue to follow N Grand Ave
- 1.4 mi
- ← 4. Turn left onto State Hwy 82 N
- 3.4 mi

**Continue on N 4514 Rd/OK-82A to your destination**

- 6 min (2.4 mi)
- ↘ 5. Turn right onto N 4514 Rd/OK-82A
- 1.4 mi
- ↘ 6. Turn right onto N Webster Rd
- 0.7 mi



↶ 7. Turn left

0.3 mi

↗ 8. Slight right

📍 Destination will be on the right

75 ft

12300 N Webster Rd  
Tahlequah, OK 74464



Housing Authority of the Cherokee Nation  
 PO Box 1007,  
 Tahlequah, Oklahoma 74465-1007  
 918-456-5482 | 1-800-837-2869

Description	Quantity	Per
<b>ESTIMATE: Rehab Estimate (Housing Authority of the Cherokee Nation)</b>		Claim #10565, Marvin Webster
<input type="checkbox"/> Approved		
<input checked="" type="checkbox"/> <b>FLOORPLAN: Floorplan</b>		

**Septic**

1 Dump Trailer, Tandem Axle	1	LD
-----------------------------	---	----

**Deck/Ramp/Termite**

2 Deck Girder Treated Pine 2"x12" - Replace	20.00 (21.00)	LF
<input type="checkbox"/> Includes 5% waste on material quantity.		
3 Deck Joists (SF), Treated Pine 2"x6", 16" o.c. - Replace	317.00 (332.85)	SF
<input type="checkbox"/> Includes 5% waste on material quantity.		
<input checked="" type="checkbox"/> This is to include construction of deck to match existing and a 5'x5' landing at the secondary entrance door.		
4 Decking, Treated Pine, 5/4" thick - Replace	317.00 (332.85)	SF
<input type="checkbox"/> Includes 5% waste on material quantity.		
<input checked="" type="checkbox"/> This is to include construction of deck to match existing and a 5'x5' landing at the secondary entrance door.		
5 Deck Railing Complete, Pressure Treated - Replace	98.00 (102.90)	LF
<input type="checkbox"/> Includes 5% waste on material quantity.		
<input checked="" type="checkbox"/> This is to include construction of deck to match existing and a 5'x5' landing at the secondary entrance door.		
6 Sidewalk, per SF - Replace	176.00	SF
7 Post, In Concrete 4"x4"x6', Treated - Replace	24 (25.20)	EA
<input type="checkbox"/> Includes 5% waste on material quantity.		
8 Deck Steps, Treated Pine, 3' Wide - Remove	3	EA
9 Deck Steps, Treated Pine, 3' Wide - Replace	3 (3.15)	EA
<input type="checkbox"/> Includes 5% waste on material quantity.		
10 Deck Joists (SF), Treated Pine 2"x6", 16" o.c. - Remove	292.00	SF
11 Deck Railing Complete, Pressure Treated - Remove	78.00	LF
12 Decking, Treated Pine, 5/4" thick - Remove	292.00	SF
13 Termite Control, Residential	2,300.00	SF
14 Post, In Concrete 4"x4"x8', Cedar - Remove	4	EA
15 Post, In Concrete 4"x4"x8', Cedar - Replace	4 (4.20)	EA
<input type="checkbox"/> Includes 5% waste on material quantity.		
<input type="checkbox"/> Treated post will be accepted. Cedar not necessary.		
16 Post, In Concrete 4"x4"x6', Treated - Remove	12	EA

**Hall Bath**

17 Pipe, PVC, Waste/Vent 3" - Replace	20.00 (21.00)	LF
<input type="checkbox"/> Includes 5% waste on material quantity.		
<input type="checkbox"/> Reconfigure and install new vent stack between hall bath and kitchen.		

Total: \_\_\_\_\_