



2014 S Muskogee Ave  
Tahlequah, OK 74464

Take State Hwy 82 N to N 435 Rd/Carbide Rd/True Rd in  
Mayes County

46 min (40.6 mi)

- ↑ 1. Head north on US-62 E  
203 ft
- ↪ 2. Turn right at the 1st cross street to stay on US-62 E  
2.2 mi
- ↑ 3. Continue straight onto OK-82 BYP/State Hwy 82 N  
① Continue to follow State Hwy 82 N  
32.2 mi
- ↶ 4. Turn left onto OK-20 W/E Ferry St  
① Continue to follow OK-20 W  
6.1 mi

Follow N 435 Rd/True Rd to US-69 N

15 min (11.0 mi)

- ↪ 5. Turn right onto N 435 Rd/Carbide Rd/True Rd  
① Continue to follow N 435 Rd/True Rd  
9.5 mi

- ↑ 6. Continue straight to stay on N 435 Rd/True Rd  
1.0 mi
- ↶ 7. Turn left onto W 390 Rd  
0.5 mi

**Follow US-69 N to E 250 Rd/W Hope Ave in Craig County**

21 min (17.9 mi)

- ↷ 8. Turn right at the 1st cross street onto US-69 N  
12.7 mi
- ↷ 9. Turn right onto US-60 E/US-69 N/U.S. Rt. 66  
3.9 mi
- ↑ 10. Continue onto N Wilson St  
0.8 mi
- ↑ 11. Continue straight onto OK-2 N/N Wilson St  
0.5 mi

**Continue on E 250 Rd/W Hope Ave. Drive to N Brown St in Vinita**

2 min (0.8 mi)

- ↶ 12. Turn left onto E 250 Rd/W Hope Ave  
0.7 mi
- ↶ 13. Turn left onto N Brown St  
Destination will be on the left  
0.1 mi

724 N Brown St  
Vinita, OK 74301

# Work Write-Up and Bid Document/By Trade

**James Shambles**

724 N Brown St. Vinita, OK 7-4464  
 (918) 323-1578

*Contractor Name:*

*Contractor Signature:*

*This document must be signed to be a valid bid.*

**PROJECT TYPE: Emergency Repairs**      **Bid Due Date:**

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<b>HVAC</b>				
<b>1 Area: EXTERIOR</b>	Ductwork/Install new Metal Insulated Duct. Tie into existing ductwork. <b>BACK SECTION of the home. Install new HVAC Exteroir Metal Insulated Duct. Tie into the existing attic duct.</b>	<b>Div.# 12.M.</b>	<b>1 Ea</b>	
<b>2 Area: CRAWLSPACE</b>	Ductwork/Repair Ductwork. Repair Ductwork <b>FRONT SECTION .Intall a section of duct to fill in/connect,the sections between the exsting duct in the Attic.</b>	<b>Div.# 12.M.</b>	<b>1 LF</b>	
<b>3 Area: EXTERIOR</b>	HVAC Equipment Replace/ Replace existing with 3.0 Ton 15 seer ELECTRIC HEAT & COOLING. COMPLETE CHANGE OUT /INCLUDING: PLENUM, FILTER GRILL, REGISTERS, THERMOSTAT, ALL WIRING & CONDENSOR LINES. CHECK; Duct Work for Leaks & make all necessary repairs. <b>FRONT SECTION of the home. Replace out side package unit and connect to the exsting exterior Duct . Install Interior Thermostat</b>	<b>Div.# 12</b>	<b>1 Ea</b>	

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<b>HVAC</b>	4 Area: EXTERIOR	Div.# 12.M.	1 Ea	
	HVAC System/Service. Service complete HVAC system. INCLUDES; Replacement of the A- Coil & Coil Box, Freon Charge,replace thermostat and Repair of line leaks See General Specifications.			
	<b>BACK SECTION of the home . Repair the HVAC to a full and complete working Heat and Air Unit.</b>			
	<b>All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement.</b>			<b>Total:</b> <input type="text"/>