



Imagery ©2025, Map data ©2025 Google 5 mi

Tahlequah
Oklahoma 74464

Take S Indian Rd and OK-100 E to S 105th St E/Ross Rd
in Muskogee County

- ↑ 1. Head south on S Muskogee Ave toward W Shawnee St

54 min (38.6 mi)

📍 Pass by BancFirst (on the right in 0.2 mi)

4.0 mi
- ↩ 2. Keep left to continue on US-62 W

223 ft
- 🔄 3. At the traffic circle, take the 2nd exit onto State Hwy 82

4.8 mi
- ➡ 4. Turn right onto S Indian Rd

15.2 mi
- ↩ 5. Turn left onto OK-10A S

2.1 mi
- ↑ 6. Continue onto OK-100 E

8.9 mi
- ➡ 7. Turn right onto US-64 W

3.5 mi

Follow S 105th St E/Ross Rd and E 273rd St S/E1140 Rd to
N Quapaw Rd/Wheeler Estates Dr in Porum

15 min (12.5 mi)

↩ 8. Turn left onto S 105th St E/Ross Rd

3.0 mi

↪ 9. Turn right onto E 213th St S/E1080

0.2 mi

↩ 10. Turn left onto S 105th St E/Ross

6.0 mi

↪ 11. Turn right onto E 273rd St S/E1140 Rd

3.0 mi

↑ 12. Continue onto Ute St

0.2 mi

↩ 13. Turn left onto N Quapaw Rd/Wheeler Estates Dr

 Destination will be on the right

384 ft

408 N Quapaw Cir

Porum, OK 74455




Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Roof (Housing Authority of the Cherokee Nation)		Claim #11631, Brandon Harkins
Approved		

ROOFPLAN: Roofplan

Roof 5, Roof 6, Roof, Roof 2

Roof area: 2,882.49 SF Squares: 28.8 SQ Soffit: 548.60 SF
Eaves: 192.62 LF Ridge: 43.46 LF



1 Shingles, Composition, Laminated/Architectural, Good - Tear Out	28.80	SQ	_____
2 Shingles, Composition, Laminated/Architectural, Good - Replace	28.80 (31.68)	SQ	_____
Includes 10% waste on material quantity.			
3 Shingles, Starter Row, Continuous - Replace	192.62 (211.88)	LF	_____
Includes 10% waste on material quantity.			
4 Ridge Cap Shingles, Laminated/Architectural - Replace	88.62 (97.48)	LF	_____
Includes 10% waste on material quantity.			
5 Felt, Single Layer, 30 lb. - Replace	28.80	SQ	_____
6 Drip Edge, Rake, Aluminum, Pre-Finished Color - Tear Out	210.54	LF	_____
7 Drip Edge, Rake, Aluminum, Pre-Finished Color - Replace	210.54 (221.06)	LF	_____
Includes 5% waste on material quantity.			
8 Gutter Apron, Aluminum, Pre-Finished Color, 5" - Tear Out	192.62	LF	_____
9 Gutter Apron, Aluminum, Pre-Finished Color, 5" - Replace	192.62 (202.25)	LF	_____
Includes 5% waste on material quantity.			
10 Valley Flashing, Aluminum - Tear Out	61.25	LF	_____
11 Valley Flashing, Aluminum - Replace	61.25 (64.31)	LF	_____
Includes 5% waste on material quantity.			

SHINGLES

UNDERLAYMENTS

VENTS AND FLASHINGS

12 Roof Vent, Static, Box/Turtle, Aluminum - Tear Out	5	EA	_____
13 Roof Vent, Static, Box/Turtle, Aluminum - Replace	5	EA	_____
14 Roof Vent, Box/Turtle - Prime & Paint	5	EA	_____
15 Flashing, Pipe Jack, Aluminum - Tear Out	3	EA	_____
16 Flashing, Pipe Jack, Aluminum - Replace	3	EA	_____
17 Flashing, Vent Pipe - Prime & Paint	3	EA	_____

DEBRIS REMOVAL

18 No debris removal is needed for this estimate. The quantity is small enough that it can be discarded with local trash pick up.			
19 Dumpster 20 Yard	1	EA	_____

Minimum Charge Adjustments

20 Minimum Charge, Painter

1 LS _____

Contractor Signature: _____

Date: _____ Total: _____