



HACN HOUSING REHAB SITE DIRECTIONS

Name: Dallis Fink

Telephone: (918) 559-2618

Address: 60551 east 346 rd
eucha, OK 74342

County: Delaware **Year Built:** 1995

GPS Coordinates: 36.29618,-95.47106 **Drive Time:**
1hr 11min

Directions: From Cherokee Nation, ok 10 north 25.5 miles at traffic circle stay straight onto 59 north 25.9 miles left onto east 346 rd destination on left

Tommy Tubbs (918) 565-2103
Cost Estimator/Inspector

2/23/2024
Date

WorkWrite-Up and Bid Document/By Trade

Dallis Fink

60551 east 346 rd Grove, OK 7-4344

(918) 559-2618

Contractor Name:

Contractor Signature:

This document must be signed to be a valid bid.

PROJECT TYPE: Emergency Repairs

Bid Due Date:

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Carpentry				
1 Area: EXTERIOR				
	Door/Exterior/6-Panel Steel/Pre-Hung/Replace. Replace exterior entrance door with new pre-hung-steel six panel door. Work shall include paint-both sides, lockset, deadbolt back door	Div.# 8.A.	1 Ea	
Roofing				
2 Area: ROOF				
	Replace Shingles / Install Heritage/30 Yr Warranty, Fiberglass shingles/Use Marlarky/Tamko or approved equal. 30 lb Felt, Painted Style D Drip Edge, Pipe Flashing, Valley Flashing, Step Flashing & Slant Back Attic vents or Ridge vents. patch area around vent hood	Div.# 7.A.	6 Sq	
Sheetmetal & Gutters				
3 Area: EXTERIOR				
	Gutters/Install/K-Style Aluminum/5". Install new "K" style Aluminum gutter (5" wide) with downspouts. over front door and down walk way in front of garage	Div.# 7.F.	50 LF	
Site Work				

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Site Work				
4	Area: ENTIRE STRUCTURE Termites-Wood Destroying Insects/Treat Structure. Treat structure for wood destroying insects. Use state licensed applicator.	Div.# 2.Q	1600 SF	
All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement.				Total: