

## HACN HOUSING REHAB SITE DIRECTIONS

кеух ю а опутит зипа

marion say wes brooks

Name Telephone: (918)/86-6468

Address: 511 sc

511 south grand grove, OK 74344

County: delaware

Year Built:

GPS Coordinates: 36.59054,-94.77026 Drive Time: 1 hour 20 min



**Directions:** From Cherokee Nation, north on us-62 E/S muskogee ave towards D0790 RD/w will;is rd 1.4 miles right onto us62 east 2.0 miles right to stay on us/62 east 1.9 miles left onto ok-10 north 25.5 miles straight at circle onto us 59 north 31.2 miles left on 6th street 377 ft right on south grand street destnation on right yellow house on corner

Tommy Tubbs (918) 565-2103

1/8/2024

Cost Estimator/Inspector

Date

## WorkWrite-Up and Bid Document/By Trade

marion Kay wesbrooks	Contractor Name:		
511 south grand grove, OK	7-4344 Contractor Signature:		
(0.0) 100 0100	This document mus	This document must be signed to be a valid bid.	id.
	PROJECT TYPE: Rehabilitation	Bid Due Date:	
Trade Work 1	Work Description / Comments Gen. Spec.	Qty Unit	Item Bid
Carpentry			
1 Area: EXTERIOR	Div.# 8.C	4 Ea	
Garage Vehicle Door/Repair over	Garage Vehicle Door/Repair overhead garage vehicle door/See Comments.		
rebuild the two wood barn style do as close as possible	rebuild the two wood barn style doors on the garage replaceing the existing and matching as close as possible		
2 Area: BEDROOM #1	<i>Div.</i> # 6.D.	70 SF	
Subfloor/ Remove and Replace/S 3/4" plywood.	Subfloor/ Remove and Replace/Small Area/3/4" Plywood. Replace subfloor with new 3/4" plywood.		
3 Area: EXTERIOR	<i>Div.</i> # 8.G	9 Ea	
Window/Replace/Vinyl Thermopa Craftsman, or use written approve screen.	Window/Replace/Vinyl Thermopane/Low-E. Replace window, White Vinyl./ American Craftsman, or use written approved equal. Includes frame, sill, sash, trim, hardware, screen.		
Flooring			
4 Area: BEDROOM #1	<i>Div.</i> # 9.L	4S8	
Vinyl Sheet Flooring/Install new vinyl floor (sheet) cowear layer and 10 year manufacturer year warranty.	Vinyl Sheet Flooring/Install new vinyl floor (sheet) covering & shoe mold. Minimum 12 mil wear layer and 10 year manufacturer year warranty.		
Paint & Finish			
Print Date: Wednesday, January 10, 2024	511 south grand grove, OK 7-4344		Page 1 of 3

Trade Wo	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Paint & Finish				
5 Area: EXTERIOR		Div.# 9.N.4	2000 SF	
House/Paint/Two Coats. Paint excaulking and filling of small holes	House/Paint/Two Coats. Paint exterior of the house (two coats). Include cleaning, caulking and filling of small holes.	leaning,		
Plumbing				
6 Areu: BEDROOM #1		Div.# 16.C.	1 Ea	
Commode/High Rise/Handica commode with Seat & two (2) Examine condition of the flang grab bars	Commode/High Rise/Handicap /Replace commode with new high rise/Handicap commode with Seat & two (2) grab bars. include new shutoff, supply line and wax ring. Examine condition of the flange and report if damaged. Consult owner for location of grab bars	dicap and wax ring. ocation of		
7 Area: BEDROOM #1		Div.# 16.C.	1 Ea	
Shower/Handicap/Pre-Fab/Insshower seat, and pressure ba	Shower/Handicap/Pre-Fab/Install Shower kit and drain, with 3-grab bars, fold down shower seat, and pressure balanced shower valve with glide bar,and shower head	old down ver head.		
Roofing				
8 Area: ROOF		Div.# 7.F	18 LF	
Flashing/Replace. Replace flashing. See comments.	ashing. See comments.			
replace flashing along gabel above sun room	above sun room			
9 Area: ROOF		Div.# 7.B.	50 SF	
Leak/Roofing/Repair/Apply LEAK STOPPER Rubberize by applying Leak Patching compound at source of leak	Leak/Roofing/Repair/Apply LEAK STOPPER Rubberized roof patch Repair roof leaks by applying Leak Patching compound at source of leak.	air roof leaks		
repair and patch around sky li	repair and patch around sky lights and any other place that might need roof patch	of patch		

attached Asbestos Sampling Report for location and testing of Planned Work Activities. Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See for conducting safe work practices that comply with OSHA Construction Standards for Asbestos compliance with the more stringent requirement. Contractor awarded the job will be responsible Based Paint requirements when applicable. Conflicts between requirements will be resolved by All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-