



Map data ©2025, Map data ©2025 Google 2 mi

Tahlequah
Oklahoma 74464

- ↑ 1. Head south on S Muskogee Ave toward W Shawnee St
 ⓘ Pass by BancFirst (on the right in 0.2 mi)
 4.1 mi
- ↻ 2. At the traffic circle, take the 2nd exit onto State Hwy 82
 14.2 mi
- ↵ 3. Turn left onto S Blue Top Rd
 8.6 mi
- ↑ 4. Continue onto S 4600 Rd/N4600 Rd/Old US Hwy 17
 1.3 mi
- ↗ 5. Slight right onto S 4610 Rd/N4610 Rd
 ⓘ Continue to follow S 4610 Rd
 3.2 mi
- ↑ 6. Continue onto S 4590 Rd/E 996 Rd/Dwight Mission Rd/N4590 Rd
 0.9 mi
- ↘ 7. Turn right
 249 ft

459111 E 996 Rd
Marble City, OK 74945



Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Structure 2 (Housing Authority of the Cherokee Nation)		
Claim #10344, Mitchell Bengé, Sr.		
Approved		
FLOORPLAN: Floorplan		

HVAC

1 Dump Trailer, Tandem Axle

1 LD

ROOFPLAN: Roofplan		
Roof, Roof 2		
Roof area: 1,916.29 SF Squares: 19.2 SQ Soffit: 362.20 SF Eaves: 109.17 LF Ridge: 77.18 LF		

METAL ROOF COVERING

2 Ribbed Roofing, Steel, Up to 1", 26 Gauge, Colored - Tear Out	19.16	SQ
3 Ribbed Roofing, Steel, Up to 1", 26 Gauge, Colored - Replace	19.16 (21.07)	SQ
Includes 10% waste on material quantity.		

METAL ROOFING EXTRAS

4 Ridge Cap, Steel - Tear Out	77.18	LF
5 Ridge Cap, Steel - Replace	77.18 (84.90)	LF
Includes 10% waste on material quantity.		
6 End Cap, Metal Ridge - Tear Out	3	EA
7 End Cap, Metal Ridge - Replace	3	EA
8 Eave Trim, Metal Roofing, 26 GA - Tear Out	109.17	LF
9 Eave Trim, Metal Roofing, 26 GA - Replace	109.17 (114.63)	LF
Includes 5% waste on material quantity.		
10 Rake Edge, Metal Roofing - Tear Out	89.06	LF
11 Rake Edge, Metal Roofing - Replace	89.06 (93.51)	LF
Includes 5% waste on material quantity.		
12 Closure Strips For Metal Panels - Replace	186.35 (195.67)	LF
Includes 5% waste on material quantity.		

FRAMING

VENTS AND FLASHINGS

13 Flashing, Neoprene Pipe Jack - Tear Out	2	EA
14 Flashing, Neoprene Pipe Jack - Replace	2	EA
15 Vent Cap, Furnace Galvanized, 4" - Tear Out	1	EA
16 Vent Cap, Furnace Galvanized, 4" - Replace	1	EA

GUTTERS / DOWNSPOUTS / FASCIA

17 Fascia, Wood Cedar 1" x 6" - Remove	198.23	LF
18 Fascia, Wood Cedar 1" x 6" - Replace	145.17 (152.43)	LF
Includes 5% waste on material quantity.		
Match Existing		
19 Fascia, Wood Cedar 1" x 6" - Replace	53.06 (55.71)	LF
Includes 5% waste on material quantity.		



Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Structure 2 (Housing Authority of the Cherokee Nation)		Claim #10344, Mitchell Bengé, Sr.
Approved		

20	Fascia - Prime & Paint	145.17	LF	_____
	Match Existing			
21	Fascia - Prime & Paint	53.06	LF	_____
22	Beaded Board Soffit - Remove	24.00	SF	_____
23	Beaded Board Soffit - Replace	24.00 (25.20)	SF	_____
	Includes 5% waste on material quantity.			
	Match Existing			
24	Soffit - Prime & Paint	24.00	SF	_____
	Match Existing			

Total: _____

Date: _____

Contractor
Signature: _____