

HACN HOUSING REHAB SITE DIRECTIONS

Name: Patsy Fisher

Telephone: (918)353-8366

Address: 15441 E 390 Rd
Jay, OK 74346

County: Delaware **Year Built:** 1970

GPS Coordinates: 36.45207, -94.73020 **Drive Time:** 1 Hr 12 Min



Directions: From Cherokee Nation, Take OK-10 N and US-59 N to E 390 Rd/E Deerlick Rd in Delaware County 1 hr 6 min (53.1 mi) Turn left onto US-62 E/S Muskogee Ave 1.9 mi Turn right onto US-62 E 2.2 mi Turn right to stay on US-62 E 1.9 mi Turn left onto OK-10 N 25.5 mi At the traffic circle, continue straight onto US-59 N Pass by NAPA Auto Parts - J & J Auto Supply (on the left in 19.3 mi) 21.5 mi Turn right onto E 390 Rd/E Deerlick Rd Continue to follow E 390 Rd Destination will be on the right 4 min (2.9 mi)

15441 E 390 Rd

Jay, OK 74346

Rodney Carman (918) 506-9858

Cost Estimator/Inspector

3/25/2025

Date

WorkWrite-Up and Bid Document/By Trade

Patsy Fisher

15441 E 390 Rd Jay, OK 7-4346

(918) 353-8366

Contractor Name:

Contractor Signature:

This document must be signed to be a valid bid.

PROJECT TYPE: Emergency Repairs

Bid Due Date:

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Roofing				
1 Area: ROOF	Roof/Build A Shed Type Roof over the porch deck. / Shed Roof. Remove old porch roof and rebuild. Work shall include all materials and labor to complete the project, including roofing materials.	Div.# 7.B.	104 SF	
2 Area: ROOF	Roofing/Heritage/30 Year Warranty. Install fiberglass shingles/Minimum 30 year warranty/Use Marlarky/Tamko or written approved equal. 30 lb Felt, Painted Style D Drip Edge, Pipe Flashing, Valley Flashing, Step Flashing & Attic vents. eliminate 30# felt and replace with synthetic underlayment. Include all materials and labor to complete the project.	Div.# 7.A.	22 Sq	
3 Area: ROOF	Roofing/Strip/Asphalt-Fiberglass. Remove all layers, and haul roofing debris to a Legal Waste Dump for disposal.	Div.# 7.C	22 Sq	

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Roofing				
4	Area: ROOF	Div.# 7.B	64 SF	
	Sheathing/Replace/Match Existing. Replace existing sheathing. Match existing as closely as possible.			
	allowing 64 sq ft for replacement			
All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement.				Total: