

**ADDENDUM #01**

**RFB 163573 – CNHS Outdoor Equipment Building**

**06/02/2025**

**PROPOSALS MUST BE RECEIVED ON OR BEFORE MONDAY JUNE 9, 2025 BY 5:00 P.M. CT TO BE CONSIDERED.**

**QUESTIONS SUBMITTED FROM INTERESTED PARTIES:**

1. Does the project have an estimated value?

Estimated cost for the project is for internal purposes only. Not intended to go out to the public.

2. Does the project have a mobilization date?

Start date will be 30 days from award.

3. Does the project have a required completion date?

Project estimated completion is 90 days from start date.

4. Are signed engineered drawings required?

The building structure will require snow and wind load verified calculations.

5. Are any utilities required?

No utilities

6. Any specifications for post frame? No

- a. Gutters No

- b. Soffits No

- c. Gauge of metal for walls and roof 26 gauge roof and walls

- d. Insulation **No**
7. Any specifications or testing required for concrete slab?
- One set of test for building slab and one set for parking apron.**
- a. PSI and Slump **4000 PSI with a 3-5 Slump**
  - b. Broom finish exterior – Slick finish interior **Yes**
  - c. Sealer required **No**
8. Overhead doors
- a. Insulated or non-insulated **Insulated**
  - b. Electric openers required **No electric openers**