

# HACN HOUSING REHAB SITE DIRECTIONS

---

**Name:** Doris Belt

**Telephone:** (918)456-1363

**Address:** 1001 S State St  
Tahlequah, OK 74464

**County:** Cherokee      **Year Built:**       

**GPS Coordinates:** 35.90314, -94827      **Drive Time:** 10 Mins

---



**Directions:** From Cherokee Nation, head northeast on US-62 / S Muskogee Ave toward S Huckleberry Cir 0.6 miles. at the traffic circle, take the 2<sup>nd</sup> exit and stay on US-62 / S Muskogee Ave 2.3 miles. continue straight onto US-62 BUS E / S Muskogee Ave 0.8 miles. turn left onto W 4<sup>th</sup> St / Fourth St 0.2 miles. Turn right onto S State Ave 0.2 miles. it will be the green house with white windows on the right.

---

Jarrold Proctor

9/9/24

Cost Estimator/Inspector

Date

## WorkWrite-Up and Bid Document/By Trade

**Doris Belt**

1001 S State St Tahlequah, OK 7-4464  
 (918) 456-1363

Contractor Name: \_\_\_\_\_

Contractor Signature: \_\_\_\_\_

*This document must be signed to be a valid bid.*

**PROJECT TYPE: Emergency Repairs**

**Bid Due Date:**

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<b>Roofing</b>				
1	Area: ROOF	Div.# 7.A.	1930 SF	<input style="width: 80px; height: 30px;" type="text"/>
Roof/Metal/R-Panel/26 gauge/36". Install new R-Panel metal roof as per manufacturer's recommendations.				
2	Area: ROOF	Div.# 7.C	20 Sq	<input style="width: 80px; height: 30px;" type="text"/>
Roofing/Strip/Asphalt-Fiberglass. Remove all layers, and haul roofing debris to a Legal Waste Dump for disposal.				
3	Area: ROOF	Div.# 7.B	128 SF	<input style="width: 80px; height: 30px;" type="text"/>
Sheathing/Replace/Match Existing. Replace existing sheathing. Match existing as closely as possible.				

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement.

**Total:**