

5014 S Muskogee Ave, Tahlequah, OK
74464 to 18832 N4320, Warner, OK 74469

Drive 46.6 miles, 53 min



Priscilla Parent



Map data ©2024 Google 10 mi

5014 S Muskogee Ave
Tahlequah, OK 74464

Continue to US-62 W

- | | | |
|---|------------------------------|-----------------|
| ↑ | 1. Head east | 53 sec (0.2 mi) |
| | | 404 ft |
| ↗ | 2. Turn right toward US-62 W | 449 ft |
| ↖ | 3. Turn left toward US-62 W | 69 ft |

Continue on US-62 W. Take US-64 E to College Rd in
Warner

- | | | |
|---|--|------------------|
| ↗ | 4. Turn right onto US-62 W | 48 min (45.0 mi) |
| | | 0.3 mi |
| ↗ | 5. Slight right toward US-62 W | 335 ft |
| ↗ | 6. Merge onto US-62 W | 20.6 mi |
| ↗ | 7. Use the right lane to merge onto OK-165 S/OK-351 via the ramp to Ft Smith | 3.2 mi |

- ↗ 8. Take the OK-165 W/Pe Blvd exit toward US-64
0.3 mi
- ↑ 9. Continue onto OK-165 W/E Peak Blvd
4.0 mi
- ↖ 10. Turn left onto the ramp to Ft. Smith
0.3 mi
- ↗ 11. Continue onto US-64 E
15.8 mi
- ↑ 12. Continue onto US-266 W
0.4 mi

Continue on College Rd. Drive to N4320

- ↗ 13. Turn right onto College Rd
4 min (1.5 mi)
- ↖ 14. Turn left onto N4320
1.0 mi
- ⓘ Destination will be on the left
0.5 mi

18832 N4320

Warner, OK 74469

Phone # 918-843-6453
918-843-6468




Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Roof (Housing Authority of the Cherokee Nation)	Claim #11013, Priscilla Parent	
 Approved		

ROOFPLAN: Roofplan

Roof, Roof 5, Roof 2, Roof 4, Roof 3

Roof area: 3,260.45 SF Squares: 32.6 SQ Soffit: 527.55 SF
Eaves: 163.24 LF Ridge: 115.88 LF



SHINGLES

1 Shingles, Laminated/Architectural Good - Tear Out	31.20	SQ
2 Shingles, Laminated/Architectural Good - Replace	31.20 (34.32)	SQ
Includes 10% waste on material quantity.		
3 Shingles, Starter Row, Continuous - Replace	125.26 (137.79)	LF
Includes 10% waste on material quantity.		
4 Ridge Cap Shingles, Fiberglass, Laminated - Replace	115.88 (127.46)	LF
Includes 10% waste on material quantity.		
5 Tear Off, Roof Covering 2 Additional Layers	31.20	SQ

UNDERLAYMENTS

6 Felt, 30LB - Replace	31.20	SQ
------------------------	-------	----

VENTS AND FLASHINGS

7 Drip Edge (Rake Only) Aluminum, Pre-Finish Color - Tear Out	111.88	LF
8 Drip Edge (Rake Only) Aluminum, Pre-Finish Color - Replace	111.88 (117.47)	LF
Includes 5% waste on material quantity.		
9 Drip Edge (Gutter Apron) Aluminum, Pre-Finish Color, 5" - Tear Out	125.26	LF
10 Drip Edge (Gutter Apron) Aluminum, Pre-Finish Color, 5" - Replace	125.26 (131.52)	LF
Includes 5% waste on material quantity.		
11 Valley Flashing, Aluminum - Tear Out	120.53	LF
12 Valley Flashing, Aluminum - Replace	120.53 (126.55)	LF
Includes 5% waste on material quantity.		
13 Chimney Flashing Large - Tear Out	1	EA
14 Chimney Flashing Large - Replace	1	EA
15 Roof Vent, Static, Box/Turtle, Aluminum - Tear Out	6	EA
16 Roof Vent, Static, Box/Turtle, Aluminum - Replace	6	EA
17 Roof Vent, Box/Turtle - Prime & Paint	6	EA
18 Flashing, Plumbing Vent Aluminum - Tear Out	2	EA
19 Flashing, Plumbing Vent Aluminum - Replace	2	EA
20 Flashing, Vent Pipe - Prime & Paint	2	EA

GUTTERS / DOWNSPOUTS / FASCIA

21 Fascia, Wood Cedar 1" x 6" - Tear Out	275.12	LF
22 Fascia, Wood Cedar 1" x 6" - Replace	275.12 (288.88)	LF
Includes 5% waste on material quantity.		
23 Fascia - Prime & Paint	275.12	LF

DEBRIS REMOVAL



Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Roof (Housing Authority of the Cherokee Nation)		Claim #11013, Priscilla Parent
Approved		

24	Modified Bitumen Asphalt, APP Cold Adhesive, Smooth Finish - Remove	1.40	SQ	_____
25	Sheathing, Roof Plywood, 1/2" - Remove	139.89	SF	_____
26	Ceiling Joists (SF) 2"x4" - 16" OC - Remove	139.89	SF	_____
27	Ceiling Joists (SF) 2"x6" - 16" OC - Replace	139.89 (146.88)	SF	_____
	Includes 5% waste on material quantity.			_____
28	Rim Joist, 2"x6" (LF) - Replace	66.00 (72.60)	LF	_____
	Includes 10% waste on material quantity.			_____
29	Ribbed Roofing, Steel, Up to 1", 28 Gauge, Colored - Replace	1.40 (1.54)	SQ	_____
	Includes 10% waste on material quantity.			_____
30	Dumpster 40 Yard	1	EA	_____

total: _____

Date: _____

Contractor
Signature: _____