

HACN HOUSING REHAB SITE DIRECTIONS

Participant: Samuel Bolin

Telephone: Home: (918) 773-8408

Business: _____

Mobile (539) 230-9394

Address: 104440 S 4510 Rd
Vian OK 74962

County: Sequoyah **Year Built:** 1968

GPS Coordinates: 35.50094,-94.99119



Directions: From Cherokee Nation, Traffic circle South on 82 left on State HWY 82 S,
Rt on Schley St, Rt on US-64 W, Rt on S. 4510
Rd, first house on left

Michael Knapp

04/07/2025

Cost Estimator/Inspector

Date




Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Roof (Housing Authority of the Cherokee Nation)		Claim #11271, Samuel Bolin
 Approved		

ROOFPLAN: Roofplan

Roof, Roof 2

Roof area: 1,442.74 SF Squares: 14.4 SQ Soffit: 306.66 SF
Eaves: 144.00 LF Ridge: 32.33 LF



SHINGLES

1 Shingles, Composition, 3-Tab, 30 Year - Tear Out	14.41	SQ	_____
2 Shingles, Composition, 3-Tab, 30 Year - Replace Includes 10% waste on material quantity.	14.41 (15.85)	SQ	_____
3 Shingles, Composition, 3-Tab, 30 Year - Replace Includes 10% waste on material quantity.	3.50 (3.85)	SQ	_____
4 Shingles, Starter Row, Continuous - Replace Includes 10% waste on material quantity.	144.00 (158.40)	LF	_____
5 Ridge Cap Shingles, 3-Tab - Replace Includes 10% waste on material quantity.	82.56 (90.82)	LF	_____

UNDERLAYMENTS

6 Felt, Single Layer, 15 lb. - Replace	14.41	SQ	_____
--	-------	----	-------

VENTS AND FLASHINGS

7 Roof Vent, Static, Box/Turtle, Aluminum - Replace	4	EA	_____
8 Valley Flashing, Aluminum - Tear Out	27.34	LF	_____
9 Valley Flashing, Aluminum - Replace Includes 5% waste on material quantity.	27.34 (28.71)	LF	_____
10 Drip Edge, Eave/Rake, Aluminum, Mill Finished - Remove	165.66	LF	_____
11 Drip Edge, Eave/Rake, Aluminum, Mill Finished - Replace Includes 5% waste on material quantity.	165.66 (173.94)	LF	_____
12 Soffit Vent, Aluminum - Replace	8	EA	_____

GUTTERS / DOWNSPOUTS / FASCIA

13 Soffit, Plywood, 3/8" - Remove	306.66	SF	_____
14 Soffit, Plywood, 3/8" - Replace Includes 5% waste on material quantity.	306.66 (321.99)	SF	_____
15 Soffit - Prime & Paint	306.66	SF	_____
16 Fascia, Cedar, 1"x6" - Tear Out	165.66	LF	_____
17 Fascia, Cedar, 1"x6" - Replace Includes 5% waste on material quantity.	165.66 (173.94)	LF	_____
18 Fascia - Prime & Paint	165.66	LF	_____

DEBRIS REMOVAL

19 Dumpster 10 Yard	1	EA	_____
---------------------	---	----	-------

Contractor Signature: _____

Claim 11271

Total: _____

Date: _____ 06/23/2025