

WorkWrite-Up and Bid Document/By Trade

Allen Davidson

48517 S. 500 Rd Salina, OK 7-4365

(918) 330-3972

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: Rehabilitation

Bid Due Date: _____

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Roofing				
1	Area: EXTERIOR Roofing/Architectural/30 Year Warranty. Install architectural shingles/Minimum 30 year warranty/Use Owens Corning "Classic" or written approved equal. Remove & replace all shingles, drip edge, felt, & flashing	Div.# 7.A.	32 Sq	<input type="text"/>
2	Area: EXTERIOR Sheathing/5/8" CDX/Replace. Replace existing sheathing/Use 5/8" CDX. Replace any damage roof decking as needed.	Div.# 7.A	320 SF	<input type="text"/>
Sheetmetal & Gutters				
3	Area: EXTERIOR Roof Jack/Replace/2". Replace plumbing roof jack / 2" pipe. Install new roof jack 1 1/2"	Div.# 5.J	1 Ea	<input type="text"/>
4	Area: EXTERIOR Roof Jack/Replace/2". Replace plumbing roof jack / 2" pipe. Install new 2" roof jack	Div.# 5.J	1 Ea	<input type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
Sheetmetal & Gutters				
5 <i>Area:</i> EXTERIOR		<i>Div.#</i> 5.J	1 Ea	<input type="text"/>
Roof Jack/Replace/4". Replace plumbing roof jack / 4" pipe. <i>Install 4" roof jack</i>				
6 <i>Area:</i> EXTERIOR		<i>Div.#</i> 5.J	4 Ea	<input type="text"/>
Vent/Install/Turbine. Install new turbine vent. <i>Install new low profile roof vents</i>				
Site Work				
7 <i>Area:</i> EXTERIOR		<i>Div.#</i>	1 SF	<input type="text"/>
Cleanup/Final. Final cleanup of entire Project. <i>Remove all trash & debris. Pick up all roofing nails w/magnet.</i>				

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.

Total: