



Map data ©2025, Map data ©2025 Google 2 mi

Tahlequah

Oklahoma 74464

- ↑ 1. Head south on S Muskogee Ave toward W Shawnee St
 ⓘ Pass by BancFirst (on the right in 0.2 mi)
 4.1 mi
- ↻ 2. At the traffic circle, take the 2nd exit onto State Hwy 82
 9.6 mi
- ↶ 3. Turn left onto OK-100 E
 3.5 mi
- ↶ 4. Turn left onto S 590 Rd
 ⓘ Destination will be on the left
 0.2 mi

participant
918-570-1479

28293 S 590 Rd

Welling, OK 74471



Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Roof (Housing Authority of the Cherokee Nation)		Claim #12236, Connie Christie
Approved		

ROOFPLAN: Roofplan 2

Roof	
Roof area: 1,881.00 SF Squares: 18.8 SQ Soffit: 337.44 SF	
Eaves: 108.00 LF Ridge: 54.00 LF	

1 Roof Panel, R-Panel, Coated Steel, Colored, 28 Gauge - Tear Out	9.50	SQ	_____
2 Roof Panel, R-Panel, Coated Steel, Colored, 28 Gauge - Replace	9.50 (10.45)	SQ	_____
Includes 10% waste on material quantity.			

METAL ROOFING EXTRAS

3 Ridge Cap, Steel, Galvanized - Tear Out	54.00	LF	_____
4 Ridge Cap, Steel, Galvanized - Replace	54.00 (59.40)	LF	_____
Includes 10% waste on material quantity.			
5 Eave Trim, Metal Roofing, 26 Gauge - Tear Out	108.00	LF	_____
6 Eave Trim, Metal Roofing, 26 Gauge - Replace	108.00 (113.40)	LF	_____
Includes 5% waste on material quantity.			
7 Rake/Edge Trim, Metal Roofing, 26 GA - Tear Out	69.68	LF	_____
8 Rake/Edge Trim, Metal Roofing, 26 GA - Replace	69.68 (73.16)	LF	_____
Includes 5% waste on material quantity.			
9 Closure Strips, Metal Panels - Replace	54.00 (56.70)	LF	_____
Includes 5% waste on material quantity.			

FRAMING

10 Sheathing, Roof, OSB, 1/2" - Tear Out	950.00	SF	_____
11 Sheathing, Roof, OSB, 1/2" - Replace	950.00 (997.50)	SF	_____
Includes 5% waste on material quantity.			

VENTS AND FLASHINGS

12 Flashing, Pipe Jack, Neoprene - Tear Out	4	EA	_____
13 Flashing, Pipe Jack, Neoprene - Replace	4	EA	_____
14 Dumpster, 10 Yard	1	EA	_____
15 Truss System, Gable, High Complexity, 4/12-6/12 - Replace	470.00	SF	_____

Total: _____

Date: _____

Contractor Signature: _____