

HACN HOUSING REHAB SITE DIRECTIONS

Name: Felecia Tiger

Telephone: (918)774-6861

Address: 104378 S 4510 Rd
Vian, OK 74962

County: Sequoyah **Year Built:** 1981

GPS Coordinates: 35.502107383370394, -94.9916166416948 **Drive Time:** 43
Mins



Directions: From Cherokee Nation,
Turn right onto US-62/S Muskogee Ave 0.8 mi At the traffic circle, take the 1st exit
onto State Hwy 82 22.5 mi Turn right onto OK-100 W/State Hwy 82 S 0.6 mi
Continue on State Hwy 82 S to Vian 10 min (8.3 mi) Turn left onto State Hwy 82
S 7.0 mi Turn right onto Old State Hwy 82/N Rodgers St 1.2 mi Continue onto N
Rodgers St 0.2 mi Take US-64 W to S 4510 Rd in Carlisle 1 min (1.1 mi) Turn right onto
Schley St 0.3 mi Continue onto US-64 W/W Schley Street Continue to follow US-64
W 0.8 mi Turn right onto S 4510 Rd Destination will be on the left 1 min (0.2 mi)

Scotty Woodard
Cost Estimator/Inspector

6/11/25
Date



Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869


Description	Quantity	Per
ESTIMATE: Roof (Housing Authority of the Cherokee Nation)		Claim #10470, Felecia Tiger
Approved		
ROOFPLAN: Roofplan		

Flue

1 Chimney Vent, All Fuel, Double Wall 12" - Remove	10.00	LF
2 Chimney Vent, All Fuel, Double Wall 12" - Replace	10.00	LF

Roof, Roof 3, Roof 2

Roof area: 2,662.26 SF **Squares:** 26.6 SQ **Soffit:** 531.48 SF
Eaves: 234.00 LF **Ridge:** 82.15 LF



SHINGLES

3 Shingles, Laminated/Architectural Good - Tear Out	26.60	SQ
4 Shingles, Laminated/Architectural Good - Replace	26.60 (29.26)	SQ
Includes 10% waste on material quantity.		
5 Shingles, Starter Row, Continuous - Replace	234.00 (257.40)	LF
Includes 10% waste on material quantity.		
6 Ridge Cap Shingles, Fiberglass, Laminated - Replace	119.71 (131.69)	LF
Includes 10% waste on material quantity.		

UNDERLAYMENTS

7 Felt, 15LB - Replace	26.60	SQ
------------------------	-------	----

VENTS AND FLASHINGS

8 Drip Edge (Gutter Apron) Aluminum, Pre-Finish Color, 5" - Tear Out	234.00	LF
9 Drip Edge (Gutter Apron) Aluminum, Pre-Finish Color, 5" - Replace	234.00 (245.70)	LF
Includes 5% waste on material quantity.		
10 Valley Flashing, Aluminum - Tear Out	26.46	LF
11 Valley Flashing, Aluminum - Replace	26.46 (27.79)	LF
Includes 5% waste on material quantity.		
12 Roof Vent, Static, Box/Turtle, Aluminum - Tear Out	8	EA
13 Roof Vent, Static, Box/Turtle, Aluminum - Replace	8	EA
14 Roof Vent, Box/Turtle - Prime & Paint	8	EA
15 Flashing, Plumbing Vent Aluminum - Tear Out	4	EA
16 Flashing, Plumbing Vent Aluminum - Replace	4	EA
17 Flashing, Vent Pipe - Prime & Paint	4	EA

DEBRIS REMOVAL

18 Drip Edge (Rake Only) Aluminum, Pre-Finish Color - Tear Out	57.92	LF
19 Drip Edge (Rake Only) Aluminum, Pre-Finish Color - Replace	57.92 (60.81)	LF
Includes 5% waste on material quantity.		
20 Dumpster 20 Yard	1	EA
21 Sheathing, Roof OSB, 1/2" - Replace	2,065.70 (2,168.99)	SF
Includes 5% waste on material quantity.		



Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869

Description	Quantity	Per
ESTIMATE: Roof (Housing Authority of the Cherokee Nation)		Claim #10470, Felecia Tiger
Approved		

Total: _____

Date: _____

Contractor
Signature: _____