

## WorkWrite-Up and Bid Document/By Trade

**Angelia Nance-Noble**

471799 E 807 Rd Stilwell, OK 7-4960

(918) 696-0703

Contractor Name: \_\_\_\_\_

Contractor Signature: \_\_\_\_\_

*This document must be signed to be a valid bid.*

**PROJECT TYPE: Rehabilitation**

**Bid Due Date:** \_\_\_\_\_

Trade	Work Description / <i>Comments</i>	Gen. Spec.	Qty Unit	Item Bid
<b>Roofing</b>				
<b>1</b>	<b>Area: ROOF</b>	<i>Div.# 7.A.</i>	30 Sq	<input type="text"/>
Replace Shingles / Install Heritage/30 Yr Warranty, Fiberglass shingles/Use Marlarky/Tamko or approved equal. 30 lb Felt, Painted Style D Drip Edge, Pipe Flashing, Valley Flashing, Step Flashing & Slant Back Attic vents.				
<i>Remove &amp; replace all shingles, felt, drip edge, flashing, pipe jacks &amp; vents.</i>				
<b>2</b>	<b>Area: EXTERIOR</b>	<i>Div.# 7.A.</i>	120 SF	<input type="text"/>
Roof/Metal/R-Panel/26 gauge/36". Install new R-Panel metal roof as per manufacturer's recommendations.				
<i>Replace metal roof and 1x4 bracing on carport.</i>				

**All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.**

**Total:**