

WorkWrite-Up and Bid Document/By Trade

#13196

1915 S Squyres ave Stilwell, OK 7-4960
(918) 575-4543

Contractor Name:

Contractor Signature:

This document must be signed to be a valid bid.

PROJECT TYPE: Rehabilitation Bid Due Date:

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Carpentry				
1	Area: ENTIRE STRUCTURE Fascia/Replace/1" x 6". Replace Fascia/ Use SmartSide Textured pre-primed Fascia material. Fastnen using recommended nails. Caulk and paint.	Div.# 6.P	200 LF	
2	Area: EXTERIOR Siding/Replace. Replace siding with new SMART SIDE PRODUCT. 4'x 8' textured. Paint 2- coats or untill full coverage	Div.# 15	800 SF	
3	Area: ENTIRE STRUCTURE Soffit/Plywood/Install. Install new soffit with new SMART SIDE PRODUCT soffit material. include chulking, paint two coats untill full coverage	Div.# 6.P	400 SF	
4	Area: ENTIRE STRUCTURE Window/Replace/Vinyl Thermopane/Low-E. Replace window, White Vinyl./ American Craftsman, or use written approved equal. Includes frame, sill, sash, trim, hardware, screen. See comments.	Div.# 8.G	13 Ea	

HVAC

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
HVAC				
5	Area: ENTIRE STRUCTURE HVAC EQUIPMENT/ Heating & Cooling, Install New 2 TON/13- 14 SEER, PACKAGE UNIT, Electric. New Metal Insulated Duct work, Includes new Electrical disconnect and wiring for a complete installation. need to be 4 ton unit	Div.# 12	1 Ea	

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.

Total: