WorkWrite-Up and Bid Document/By Trade

#13167

202 S. Caddo St. Muldrow, OK 7-4948

(479) 650-0784

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: **Rehabilitation** **Bid Due Date:**

Trade	*Work Description / Comments*	*Gen. Spec.*	*Qty Unit*	*Item Bid*
Concrete				
1	***Area:*** **FOUNDATION**	*Div.#* NA	12 Ea	
	Foundation/ Repair/ Install steel driven Helical Piers to rock or load bearing strata. Lift and support concrete foundation.include any interior concrete work or use of poly foam if needed. Include hydro plumbing test if needed to check for leaks.			
2	***Area:*** **FOUNDATION**	*Div.#* NA	14 Ea	
	Foundation/ Repair/ Install steel driven Helical Piers to rock or load bearing strata. Lift and support concrete foundation.include any interior concrete work or use of poly foam if needed. Include hydro plumbing test if needed to check for leaks.			

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.

Total: