
Housing Authority of the Cherokee Nation
PO Box 1007,
Tahlequah, Oklahoma 74465-1007
918-456-5482 | 1-800-837-2869

#14559

Description	Quantity	Per
ESTIMATE: Emergency 2 (Housing Authority of the Cherokee Nation)		
Approved		
EXTERIOR PLAN: Exterior Plan		
General Items		
1 Dumpster, 20 Yard	1	EA
ROOFPLAN: Roofplan		
Roof, Roof 2, Roof 3, Roof 4, Roof 5		
Roof area: 3,322.63 SF **Squares:** 33.2 SQ **Soffit:** 546.36 SF **Eaves:** 149.51 LF **Ridge:** 108.66 LF		
2 Shingles, Composition, Laminated/Architectural, Very Good - Tear Out	33.24	SQ
3 Shingles, Composition, Laminated/Architectural, Very Good - Replace	33.24 (36.56)	SQ
Includes 10% waste on material quantity.		
4 Roof Vent, Static, Box/Turtle, Aluminum - Replace	6	EA
5 Sheathing, Roof, OSB, 1/2" - Replace	1,194.18 (1,253.89)	SF
Includes 5% waste on material quantity.		
6 Felt, Single Layer, 30 lb. - Replace	33.24 (34.90)	SQ
Includes 5% waste on material quantity.		
7 Shingles, Starter Row, Eave, Continuous - Replace	149.51 (158.48)	LF
Includes 6% waste on material quantity.		
8 Drip Edge, Eave/Rake, Aluminum, Mill Finished - Replace	307.72 (323.11)	LF
Includes 5% waste on material quantity.		
9 Valley Flashing, Painted, Galvanized Steel - Replace	76.53 (80.36)	LF
Includes 5% waste on material quantity.		
10 Valley Flashing, Painted, Galvanized Steel - Remove	76.53	LF
11 Valley Flashing, Painted, Galvanized Steel - Tear Out	76.53	LF
12 Flashing, Neoprene Pipe Jack - Replace	4	EA
13 Ridge Cap Shingles, 3-Tab - Replace	108.66 (119.54)	LF
Includes 10% waste on material quantity.		
14 Gutter, Box, Aluminum, 5" - Replace	60.00 (63.00)	LF
Includes 5% waste on material quantity.		
with down spouts same color as the front guttering put exta hanger to hold up cause of so long of run take the front guttering down while roofing and reset when done with roof		

Total: _____

Date: _____

Contractor Signature: _____