WorkWrite-Up and Bid Document/By Trade

#146446

1904 S Muskogee Pl Claremore, OK 7-40
(918) 710-0237

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: **Emergency Repairs** **Bid Due Date:**

Trade	*Work Description / Comments*	*Gen. Spec.*	*Qty Unit*	*Item Bid*
Carpentry				
1	***Area:*** **ATTIC** Access Door/Replace. Replace access door. replace attic access door	*Div.#* 8.A.1. D	1 Ea	
2	***Area:*** **BATHROOM #1** Grab Bar Backing/Open Wall/Install backing for grab bars. Install 2" x 8" backing (blocking) for grab bar(s) in open wall. in and around shower	*Div.#* 11.A. 3	12 LF	
Concrete				
3	***Area:*** **BATHROOM #1** Floor/Concrete/Repair Cracks. Repair cracks in concrete Floor. Clean the cracked area and fill with Epoxy Concrete Sealant. See General Specifications for required repairs. repair in front of shower	*Div.#* 3.Q	5 LF	

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Concrete				
4	***Area:*** **EXTERIOR**	*Div.#* 3.O	24 SF	
	Sidewalk/Concrete/Install. Install new concrete Sidewalk. 4" minimum thickness. raise sidewalk level with driveway			
Drywall & Finish				
5	***Area:*** **BATHROOM #1**	*Div.#* 9.D	64 SF	
	Drywall/Moisture Resistant/Replace. Replace drywall with moisture resistant drywall-1/2".includes mud, tape and finish. remove drywall around the shower and install bracing for grab bars			
Electrical				
6	***Area:*** **ELECTRICAL**	*Div.#* 13.D. 22	1540 SF	
	Elect.System/Check all wiring, Replace/outlets, switches, fixtures and devices,/ Make all repairs necessary to meet NEC requirements. check all wiring , replace plugs , switches, and gfci's			
7	***Area:*** **ELECTRICAL**	*Div.#* 13.D. 1.	1 Ea	
	Main Service Repair/200 Amp Service Center/ Replace Main Breaker. Replace/Repair service Wire Connections. Existing Main Service Panel.			
Plumbing				
8	***Area:*** **BATHROOM #1**	*Div.#* 16.C.	1 Ea	
	Shower/Elderly/Pre-Fab Install new elderly shower/Pre-fab 3 or 4 piece / with 3-grab bars, Includes a pressure balanced shower valve, glide bar,shower head, drain line, sheetrock and paint to match.			

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement.

Total: