



*Housing Authority of the Cherokee Nation
1500 Hensley Drive
P.O. Box 1007
Tahlequah, OK 74465-1007
Phone 918-456-5482*



Solicitation 2026-001-007- Cherokee County.

Please insert the **CORRECTED – “REVISED- MANDATORY BID RESPONSE SHEET**. (Attached) identifying the requirements concerning the water line extension to include 450’ of 2” Poly with welded butt joints.

Revised Mandatory Bid Response sheet, Drug Free and Tobacco Free Workplace, Indian Preference in Employment and training opportunities, Statement on Providing Cherokee or Indian Preference in the award of subcontracts, Preparation Outline, Non-Collusive Affidavit, Supplemental Bid information on Septic Systems, Supplemental Bid information on Well Systems and this addendum notification must be submitted with your bid in order for your bid to be considered. Failure to submit the required and corrected documents supplied in the bid packet and all addenda and your bid will be considered non responsive.

Should any addenda be issued prior to submission of this bid, bidder acknowledges receipt of same by initials and date of the following addenda.

ADDENDUM #1 _____

ADDENDUM #2 _____



**REVISED- MANDATORY BID RESPONSE SPREADSHEET – HACN
BID SOLICITATION # 2026-001-007**

The General Contractor, as Bidder, agrees to perform all work as shown and called for in the scope of work and specifications for the HACN.

The work will be completed within 120 workdays of acceptance of this proposal, a fully executed contract, and receipt of a Notice to Proceed. The Bidder agrees to furnish all necessary labor, quality control, licenses, material, equipment, tools, supplies, permits, insurance and supervision to complete the entire project and to perform the work required thereof.

This unit should be built as designed on the site evaluation, and the inspector will need to be notified to proceed with ALL DIRT WORK cautiously.

UNIT 75166

3-BR - Gable Roof - Bid Amount \$ _____

RW- Requirements:

450' of 2" Poly with welded butt joints:

Include membership fees, meter tap and a flush valve blow off at the end of the line.

Include 6" of screenings above and below the pipe for bedding.

Include 30' of 6" PVC for sleeving the Poly at the road crossing.

Familiarize the dig site, extremely rocky.

Septic Systems and Wells will be provided via a separate bid (bid form provided by HACN).

NOTE TO BIDDERS REGARDING (CHEROKEE) TRIBAL OR INDIAN PREFERENCE:

TERO Certified Contractor: _____ YES _____ NO (check one)
(Proof of Certification must accompany all bids)

By signing this bid document, I understand that after the home has been completed, I will be held to a 1-Year Warranty Period.

SUBMITTED BY:

COMPANY NAME

COMPANY ADDRESS

PRINT NAME & TITLE

AUTHORIZED SIGNATURE

EMAIL ADDRESS

PHONE NUMBER