

HACN HOUSING REHAB SITE DIRECTIONS

#12103

Telephone: (918)235-4184

Address: 309 N Dennis St
Vian, OK 74962

County: Sequoyah Year Built: 1980

GPS Coordinates: 35.50380,-94.97440 Drive Time: 40 min

4-Bedroom



Directions: From Cherokee Nation, Take 82 S 23.1 mi turn left at McQuicks to stay on 82 S go 8 mi turn right on E 1041 Rd at Snack Mart go 0.3 mi turn left on N Rodgers St/Old state Hwy 82 go 0.1 mi stay to the right on Dennis St house is on the right

Maurice Gifford 918-506-9860
Cost Estimator/Inspector

8/27/25
Date

WorkWrite-Up and Bid Document/By Trade

#12103

309 N Dennis St Vian, OK 7-4962

(918) 235-4184

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: Emergency Repairs

Bid Due Date: _____

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<u>Carpentry</u>				
1	Area: BATHROOM #1 Base Trim/Pine, K- Pattern 2-1/4" Solid/ Stain Grade /Replace. Replace base trim, K-Trim, solid pine,2-1/4". Stain & Finish.	Div.# 6.N	12 LF	<input style="width: 80px; height: 40px;" type="text"/>
2	Area: BATHROOM #1 Overlay sub-floor with 3/8 AC plywood.	Div.# 9.L.3	32 SF	<input style="width: 80px; height: 40px;" type="text"/>
3	Area: BATHROOM #1 Passage Door, Jamb & Trim/Pre-Hung/Flush-Faced/Replace passage door & lockset with new pre-hung luan/ flush faced, stain grade jamb and trim. Work shall include Stain & Clear Coat to match..	Div.# 8.A	1 Ea	<input style="width: 80px; height: 40px;" type="text"/>
<i>Move door closer to linen closet to make room for vanity</i>				
4	Area: BATHROOM #1 Sinktop/Cultured Marble/Integral Sink. Replace existing sinktop with new cultured marble sink top with integral sink. Include new drain line, trap & Delta faucet.	Div.# 11.4.	8 SF	<input style="width: 80px; height: 40px;" type="text"/>
5	Area: BATHROOM #1 Subfloor/ Remove and Replace/Small Area/3/4" Plywood. Replace subfloor with new 3/4" plywood.	Div.# 6.D.	32 SF	<input style="width: 80px; height: 40px;" type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<u>Carpentry</u>				
6	<i>Area:</i> BATHROOM #1 Vanity Base Cabinet/Pre-Finished Oak. Replace existing vanity with new pre-finished oak vanity base cabinet.	Div.# 6.O	4 LF	<input type="text"/>
7	<i>Area:</i> BATHROOM #1 Window/Replace/Vinyl Thermopane/Low-E. Replace window, White Vinyl./ American Craftsman, or use written approved equal. Includes frame, sill, sash, trim, hardware, screen. <i>Case inside out with wood</i>	Div.# 8.G	1 Ea	<input type="text"/>
8	<i>Area:</i> UTILITY ROOM #1 Window/Replace/Vinyl Thermopane/Low-E. Replace window, White Vinyl./ American Craftsman, or use written approved equal. Includes frame, sill, sash, trim, hardware, screen. <i>Laundry room</i>	Div.# 8.G	1 Ea	<input type="text"/>
<u>Drywall & Finish</u>				
9	<i>Area:</i> BATHROOM #1 Drywall/Wall/Replace 1/2" drywall on wall/Finish completely. Work shall include tape,bed,texture and paint to match existing surfaces. <i>Remove marlite do not include paint it will be on a seperate line item. Also remove wall heater. Use moisture resistant sheetrock</i>	Div.# 9.D	133 SF	<input type="text"/>
<u>Electrical</u>				
10	<i>Area:</i> BATHROOM #1 Light Fixture/Heat-Vent-Light/Install new bathroom light (100 watt), heater (1450 watt), vent fan (70 CFM) and switch. Fan shall be vented out of attic to code. <i>Replace exsisting</i>	Div.# 13.D. 16	1 Ea	<input type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
Electrical				
11	<i>Area:</i> ELECTRICAL	Div.# 13.D. 1	1 Ea	<input type="text"/>
Main Service/200 Amp/Replace. Replace existing main service with new 200 Amp main service with 18 branch breakers.				
12	<i>Area:</i> BATHROOM #1	Div.# 13.D. 6	1 Ea	<input type="text"/>
Outlet/Interior/110 GFCI & Circuit/Install new 110v GFCI wall outlet & circuit/Interior. Use wire from wall heater and install a GFCI above vanity				
Flooring				
13	<i>Area:</i> BATHROOM #1	Div.# 9.L	4 SY	<input type="text"/>
Vinyl Sheet Flooring/Install new vinyl floor covering & shoe mold. Minimum 12 mil wear layer and 10 year manufacturer year warranty. Use a heavy floor roller over new flooring				
HVAC				
14	<i>Area:</i> HVAC	Div.# 12	1960 SF	<input type="text"/>
Ductwork/Install new ductwork/SF = air conditioned floor area. Install supply and return air ductwork. Seal return air plenums including boxes under(Split Unit) unit and closet ceiling to insure no Attic air is pulled into unit. Run ductwork from package unit includes return air and all ceiling registers. There is no existing				
15	<i>Area:</i> HVAC	Div.# 12	1 Ea	<input type="text"/>
HVAC EQUIPMENT/ Heating & Cooling, Install New 2 TON/13- 14 SEER, PACKAGE UNIT,Electric. New Metal Insulated Duct work, Includes new Electrical disconnect and wiring for a complete installation. There is no existing HVAC. Size unit to Sq footage of the house				
Paint & Finish				

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
Paint & Finish				
16	Area: BATHROOM #1 Paint Interior /Ceilings, Walls, & Trim /Paint Two coats, . Work shall include minor repairs to surfaces. SF=ACTUAL SURFACE AREA OF WALLS & CEILING. Paint entire bathroom	Div.# 9.N.3	180 SF	<input type="text"/>
Plumbing				
17	Area: BATHROOM #1 Commode/Install new commode, seat, supply line, shutoff, flange and wax seal. Use American Standard Cadet or written approved equal.	Div.# 11.A	1 Ea	<input type="text"/>
18	Area: BATHROOM #1 Leak/Plumbing. Repair leak/see comments. Repair drain from kitchen sink it has came loose under bathroom floor	Div.# 11.A	1 Ea	<input type="text"/>
19	Area: BATHROOM #1 Shower/ Tub Acrylic Fiberglass/Pre-Fab/ Replace existing bathtub/shower combination with new American Standard Standard Fit. Include all plumbing & fixtures.	Div.# 11.A	1 Ea	<input type="text"/>
All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement.				Total: <input type="text"/>