

Work Write-Up and Bid Document/By Trade

#13235

39559 S 500 rd Eucha, OK 7-4342
 (539) 228-1343

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: Rehabilitation

Bid Due Date: _____

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Carpentry				
1	Area: KITCHEN Cabinets, Base Kitchen/Replace/ Prefinished Oak. Replace Base Cabinets, Includes, door and drawer pulls.	Div.# 6.O.1	18 LF	<input type="text"/>
2	Area: KITCHEN Cabinets, Wall Hung/ Replace/Pre-Finished Oak/3/4" Lumber Core/. Replace wall hung cabinet(s) with new pre-finished oak cabinet(s).	Div.# 6.O.2	18 LF	<input type="text"/>
3	Area: KITCHEN Countertop/ Plywood & Laminate/Replace. Remove existing countertop and replace with new site built Plywood & laminate countertop and backsplash.	Div.# 6.O.4	18 LF	<input type="text"/>
4	Area: EXTERIOR Door/Exterior/6-Panel Steel/Pre-Hung/Replace. Replace exterior entrance door with new pre-hung-steel six panel door. Work shall include paint-both sides, lockset, deadbolt	Div.# 8.A.	2 Ea	<input type="text"/>

Electrical

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
Electrical				
5	<i>Area:</i> ENTIRE STRUCTURE	<i>Div.</i> # 13.D. 22	1200 SF	<input type="text"/>
Elect. System/Check all wiring, Replace/outlets, switches, fixtures and devices./ Make all repairs necessary to meet NEC requirements.				
Paint & Finish				
6	<i>Area:</i> EXTERIOR Fascia/ Paint fascia/fascia two coats.	<i>Div.</i> # 9.N.4	170 LF	<input type="text"/>
7	<i>Area:</i> EXTERIOR Siding/Paint Siding/Two Coats. include soffit	<i>Div.</i> # 9.N	400 SF	<input type="text"/>
<p>All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.</p>				
Total:				<input type="text"/>