

# WorkWrite-Up and Bid Document/By Trade

#14508

17360 Redbud Dr Catoosa, OK 7-4015  
 (918) 845-3709

Contractor Name: \_\_\_\_\_

Contractor Signature: \_\_\_\_\_

*This document must be signed to be a valid bid.*

**PROJECT TYPE: Emergency Repairs**      **Bid Due Date:**

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<b>Roofing</b>				
1	<b>Area: ROOF</b> Replace Shingles / Install Heritage/30 Yr Warranty, Fiberglass shingles/Use Marlarky/Tamko or approved equal. 30 lb Felt; Painted Style D Drip Edge, Pipe Flashing, Valley Flashing, Step Flashing & Slant Back Attic vents.	Div.# 7.A.	24 Sq	<input style="width: 50px; height: 30px;" type="text"/>
2	<b>Area: ROOF</b> Roofing/Roll Roofing/90 lb./Replace. Remove up to one layer of roll roofing and install new 90 pound rolled roofing. Use peel and seal rolled roofing over porch area	Div.# 7.D	1 Sq	<input style="width: 50px; height: 30px;" type="text"/>
3	<b>Area: ROOF</b> Roofing/Strip/Asphalt-Fiberglass. Remove all layers, and haul roofing debris to a Legal Waste Dump for disposal.	Div.# 7.C	24 Sq	<input style="width: 50px; height: 30px;" type="text"/>
4	<b>Area: ENTIRE STRUCTURE</b> Sheathing/5/8" OSB/ Replace. Replace existing sheathing/Use 5/8" OSB.	Div.# 7.A	2107 SF	<input style="width: 50px; height: 30px;" type="text"/>

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
-------	-----------------------------	------------	----------	----------

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement.

**Total:**