

WorkWrite-Up and Bid Document

Ashley Stilwell
 910 Chestnut Circle
 Vian, OK
 74962-
 (918) 525-2221

Contractor Name _____

Contractor Signature _____

Bid Due Date:

<i>Trade</i>	<i>Area</i>	<i>Description</i>	<i>Comments</i>	<i>Manual Spec</i>	<i>Quantity</i>	<i>Enter Bid</i>
--------------	-------------	--------------------	-----------------	--------------------	-----------------	------------------

Appliances

INTERIOR

1		Dishwasher. Install new dishwasher	replace dishwasher	10.F.	1 EA	
2		Range Oven/30"/Free Standing. Install new 30" range/oven.	replace stove	10.F	1 EA	
3		Refrigerator/18.2 CF/ Install new Fridge	replace fridge	10.F	1 EA	

Carpentry

EXTERIOR

4		Door/Exterior/6-Panel Steel/Pre-Hung/Replace. Replace exterior entrance door with new pre-hung-steel six panel. Use Stanley #13757 or written approved equal. Work shall include paint-both sides.	replace exterior doors	8.A.	4 EA	
---	--	--	------------------------	------	------	--

<i>Trade</i>	<i>Area</i>	<i>Description</i>	<i>Comments</i>	<i>Manual Spec</i>	<i>Quantity</i>	<i>Enter Bid</i>
--------------	-------------	--------------------	-----------------	--------------------	-----------------	------------------

Carpentry

EXTERIOR

5		Storm Door/Vinyl Clad/Replace storm/screen door with new self storing storm door/Vinyl Clad/Use Larson model 298-SS or written approved equal.	replace storm doors	8.B	4 EA	<input type="text"/>
----------	--	--	---------------------	-----	------	----------------------

Electrical

INTERIOR

6		Smoke Detector/Battery Operated/Install new smoke detector, battery operated (10 year lithium battery). All bedrooms and hallways adjacent to bedrooms. Use Firex #4015 or written approved equal.	replace smoke detectors	13.D.11	4 EA	<input type="text"/>
----------	--	--	-------------------------	---------	------	----------------------

Flooring

INTERIOR

7		Carpet & Pad/Level Loop/26 oz./Install new carpet (26 oz., level loop)and pad (15 oz.).	remove and replace carpet	9.M	105 SY	<input type="text"/>
8		Vinyl Flooring/Repair existing vinyl flooring/See comments.	strip, clean and wax tile	9.L	160 SF	<input type="text"/>

Paint & Finish

INTERIOR

<i>Trade</i>	<i>Area</i>	<i>Description</i>	<i>Comments</i>	<i>Manual Spec</i>	<i>Quantity</i>	<i>Enter Bid</i>
<i>Paint & Finish</i>						
	INTERIOR					
9		Interior Surfaces/Paint all interior surfaces of structure - Two Coats. Entire interior excluding kitchen and bath cabinets. Work shall include minor repairs to all surfaces. SF=FLOOR AREA OF ENTIRE STRUCTURE.	Touch up interior as needed	9.N.	1 SF	<input type="text"/>
<i>Plumbing</i>						
	INTERIOR					
10		Commode & Seat/Install new commode, seat, supply line, shutoff and wax seal. Use American Standard Cadet or written approved equal.	replace stools	11.A	2 EA	<input type="text"/>
<i>Site Work</i>						
	INTERIOR					
11		Cleanup/Final. Final cleanup of entire Project.	remove all trash and debris clean interior and exterior of home, mow yard		1 SF	<input type="text"/>
TOTAL						<input type="text"/>