

WorkWrite-Up and Bid Document

Gina Brumley

906 Chestnut Circle

Vian, OK

74962-

(918) 525-2221

Contractor Name _____

Contractor Signature _____

Bid Due Date: _____

Trade	Area	Description	Comments	Manual Spec	Quantity	Enter Bid
<i>Appliances</i>						
	INTERIOR					
1		Dishwasher. Install new dishwasher	replace dishwasher	10.F.	1 EA	<input type="text"/>
2		Fire protection (Kiddie1-A : 10-B-C rec. fire extinguisher).	replace extinguisher	10.F	1 EA	<input type="text"/>
3		Range Oven/30"/Free Standing. Install new 30" range/oven.	replace oven	10.F	1 EA	<input type="text"/>
4		Refrigerator/18.2 CF/ Install new Fridge	replace fridge	10.F	1 EA	<input type="text"/>
5		Vent/Install/Dryer. Install new louvered dryer vent with ducting.	replace dryer vent	10.D.2.D.	1 EA	<input type="text"/>

<i>Trade</i>	<i>Area</i>	<i>Description</i>	<i>Comments</i>	<i>Manual Spec</i>	<i>Quantity</i>	<i>Enter Bid</i>
<i>Appliances</i>						
	INTERIOR					
6		Vent-A-Hood/30"/Ext. Vented/Install new kitchen vent-a-hood (ext.vent)/30"	replace venthood	10.D.3.D	1 EA	<input type="text"/>
<i>Carpentry</i>						
	EXTERIOR					
7		Door/Exterior/6-Panel Steel/Pre-Hung/Replace. Replace exterior entrance door with new pre-hung-steel six panel. Use Stanley #13757 or written approved equal. Work shall include paint-both sides.	replace exterior entry doors	8.A.	4 EA	<input type="text"/>
8		Storm Door/Vinyl Clad/Replace storm/screen door with new self storing storm door/Vinyl Clad/Use Larson model 298-SS or written approved equal.	replace storm doors	8.B	4 EA	<input type="text"/>
9		Window Screen/Repair window screen as per General Specifications.	replace all screens on home	8.I	7 EA	<input type="text"/>
	INTERIOR					
10		Base Trim/Pine Colonial 2-1/4" Fingerjoint/Replace. Replace base trim, colonial, fingerjoint,2-1/4" pine.	remove and replace interior trim, paint white	6.N	450 LF	<input type="text"/>

<i>Trade</i>	<i>Area</i>	<i>Description</i>	<i>Comments</i>	<i>Manual Spec</i>	<i>Quantity</i>	<i>Enter Bid</i>
<i>Carpentry</i>						
	INTERIOR					
11		Countertop/Replace. Remove existing countertop and replace with new countertop and backsplash.	replace countertops and backsplash	6.O.4	12 LF	<input type="text"/>
12		Paper Holder/Replace paper holder	replace paper holders	10.E.2.	2 EA	<input type="text"/>
13		Passage Door/Pre-Hung/6-Panel/Replace passage door & lockset with new pre-hung 6-Panel. Work shall include paint both sides.	replace all interior doors	8.A	12 EA	<input type="text"/>
14		Towel Bar/Install new towel bar/24".	replace towel bars in bathrooms	10.E.2.	4 EA	<input type="text"/>
<i>Electrical</i>						
	EXTERIOR					
15		Light Fixture/Porch/Replace exterior porch light.	replace porch lights	13.D.9	3 EA	<input type="text"/>
	INTERIOR					
16		Ceiling Fan & Light Kit/52"/Install ceiling fan (52") with light kit, switch, cover plate and wiring/Use Hunter "Greenwich" or written approved equal (lifetime warranty).	replace all ceiling fans	13.D.9.B	4 EA	<input type="text"/>

<i>Trade</i>	<i>Area</i>	<i>Description</i>	<i>Comments</i>	<i>Manual Spec</i>	<i>Quantity</i>	<i>Enter Bid</i>
<i>Electrical</i>						
	INTERIOR					
17		Cover Plate/Outlet/Install new outlet cover plate	remove and replace all plugs, outlets, cover plates	13.D.6.	20 EA	<input type="text"/>
18		Light Fixture & Switch/Wet Area/Replace. Replace existing light fixture and switch with new wet-area approved light fixture and switch.	replace barlights in both bathrooms	13.D.	2 EA	<input type="text"/>
19		Light Fixture, Switch & Circuit/Room/Install new semi-flush mount ceiling light fixture, switch, cover plate and circuit. Use Angelo model 66201.	replace all interior lights	13.D.9	11 EA	<input type="text"/>
20		Light Fixture/Heat-Vent-Light/Install new bathroom light (100 watt), heater (1450 watt), vent fan (70 CFM) and switch. Use Broan model 655 or written approved equal.	replace heat vent light in both bathrooms	13.D.16	2 EA	<input type="text"/>
21		Smoke Detector/Battery Operated/Install new smoke detector, battery operated (10 year lithium battery). All bedrooms and hallways adjacent to bedrooms. Use Firex #4015 or written approved equal.	replace smoke detectors	13.D.11	5 EA	<input type="text"/>

Flooring

INTERIOR

<i>Trade</i>	<i>Area</i>	<i>Description</i>	<i>Comments</i>	<i>Manual Spec</i>	<i>Quantity</i>	<i>Enter Bid</i>
<i>Flooring</i>						
	INTERIOR					
22		Carpet & Pad/Level Loop/26 oz./Install new carpet (26 oz., level loop)and pad (15 oz.).	remove and replace carpet	9.M	100 SY	<input type="text"/>
23		Vinyl Floor Tile/Install new vinyl floor tile/12" x 12" x 1/8".	remove and replace tile in designated areas	9.L	360 SF	<input type="text"/>
<i>Paint & Finish</i>						
	INTERIOR					
24		Interior Surfaces/Paint all interior surfaces of structure - Two Coats. Entire interior excluding kitchen and bath cabinets. Work shall include minor repairs to all surfaces. SF=FLOOR AREA OF ENTIRE STRUCTURE.	paint interior, to include all closets use off white	9.N.	1350 SF	<input type="text"/>
<i>Plumbing</i>						
	INTERIOR					
25		Commode & Seat/Install new commode, seat, supply line, shutoff and wax seal. Use American Standard Cadet or written approved equal.	replace stools in bathrooms	11.A	2 EA	<input type="text"/>

<i>Trade</i>	<i>Area</i>	<i>Description</i>	<i>Comments</i>	<i>Manual Spec</i>	<i>Quantity</i>	<i>Enter Bid</i>
<i>Plumbing</i>						
	INTERIOR					
26		Faucet/Kitchen. Install new kitchen faucet (Use Delta single-handle model 100-WF or written approved equal), supply lines & shutoffs.	replace faucet in kitchen	11.A	1 EA	<input type="text"/>
27		Faucet/Vanity/Install new vanity faucet, supply lines & shutoffs. Use Moen one handle # P84521 or written approved equal.	replace faucet in both bathrooms	11.A	2 EA	<input type="text"/>
28		Shower Faucet & Diverter/Install new bath/shower faucet with diverter. Use Delta model N1348 or written approved equal.	replace faucet, diverter, and head in both bathrooms	11.A	2 EA	<input type="text"/>
29		Water Heater/Gas/40 Gallon/Install new 40 gal. gas water heater. Work shall include elevating to 18" (if in garage), replacement of TPR, all combustion air and gas & electrical hook-ups for code legal installation.	replace water heater	11.A	1 EA	<input type="text"/>
<i>Site Work</i>						
	EXTERIOR					
30		Cleanup/Final. Final cleanup of entire Project.	power wash all vinyl, remove all trash, remove all exterior trash mow yard.		1 SF	<input type="text"/>

<i>Trade</i>	<i>Area</i>	<i>Description</i>	<i>Comments</i>	<i>Manual Spec</i>	<i>Quantity</i>	<i>Enter Bid</i>
TOTAL						<input type="text"/>