

WorkWrite-Up and Bid Document/By Trade

Angela Whittmore

23479 E. 758 Rd. Tahlequah, OK 7-4464

(918) 931-5539

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: Rehabilitation

Bid Due Date: _____

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<u>Carpentry</u>				
1	Area: KITCHEN Fire Extinguisher/Install. Install new fire extinguisher.	Div.# 10.G	1 Ea	<input style="width: 80px; height: 40px;" type="text"/>
<u>Electrical</u>				
2	Area: INTERIOR Smoke Detector/Hard Wired with Battery Back-Up/Install new smoke detector, hard wired with battery backup. All bedrooms and hallways adjacent to bedrooms. Use Firex #045186 or written approved equal. Instal in kitchen, hallway and all bedrooms.	Div.# 13.D. 11	5 Ea	<input style="width: 80px; height: 40px;" type="text"/>
<u>HVAC</u>				
3	Area: INTERIOR HVAC Equipment/Central/Cooling/ Heating/3 TON/13 SEER. Replace All existing HVAC equipment (13 SEER). INSIDE FURNACE AND OUTSIDE EQUIPMENT/CONDENSOR COIL, EVAP, NEW DISCONNECT, NEW HIGH & LOW COPPER LINES. Complete Change out. Propane unit.	Div.# 12	1 Ea	<input style="width: 80px; height: 40px;" type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
--------------	------------------------------------	-------------------	-----------------	-----------------

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.

Total: