

WorkWrite-Up and Bid Document/By Trade

Greg Claypool

2100 W. 25th North Muskogee, OK 7-440

(918) 683-1265

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: Rehabilitation

Bid Due Date: _____

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<u>Carpentry</u>				
1	Area: KITCHEN Fire Extinguisher/Install. Install new fire extinguisher.	Div.# 10.G	1 Ea	<input style="width: 80px; height: 30px;" type="text"/>
<u>Electrical</u>				
2	Area: INTERIOR Smoke Detector/Battery Operated/Install new smoke detector, battery operated (10 year lithium battery). All bedrooms and hallways adjacent to bedrooms. Use Firex #4015 or written approved equal.	Div.# 13.D. 11	5 Ea	<input style="width: 80px; height: 30px;" type="text"/>
<u>Plumbing</u>				
3	Area: GARAGE Water Heater/ Natural Gas/40 Gallon. Replace water heater with a new 40 gal. gas water heater. Work shall include elevating to 18" (if in garage), TPR, combustion air, Gas Flex line, Flex water supply connections, and drain Pan. Code Legal Installation.	Div.# 11.A	1 Ea	<input style="width: 80px; height: 30px;" type="text"/>
<u>Roofing</u>				

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Roofing				
4	Area: EXTERIOR	Div.# 7.A.	30 Sq	
Roofing/Heritage/30 Year Warranty. Install fiberglass shingles/Minimum 30 year warranty/Use Marlarky/Tamko or written approved equal. 30 lb Felt, Style D Drip Edge, Pipe Flashing, Valley Flashing. Replace all damaged decking.				

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.

Total: