WorkWrite-Up and Bid Document/By Trade

| = | Contractor Name: | | Karr |
|---|---|--|-----------|
| (918) 696-4244 | Contractor Signature: | | |
| | This docume | This document must be signed to be a valid bid | id bid. |
| | PROJECT TYPE: Rehabilitation | Bid Due Date: | |
| Trade Work Descripti | Work Description / Comments Gen. Spec. | Qty Unit | Item Bid |
| Flooring | | | |
| 1 Area: BATHROOM #1 | <i>Div.</i> # 9.L | 6 SY | |
| Vinyl Sheet Flooring/Install new vinyl floor (sheet) cowear layer and 10 year manufacturer year warranty. REPLACE EXISTING SHEET VINYL. | vering & shoe mold. Mini | | |
| Plumbing | | | |
| 2 Area: BATHROOM #1 | Div.# 16.C. | C. 1Ea | |
| Commode/High Rise/Replace existing co (2) grab bars. Work shall include new st condition of the flange and report if dama | Commode/High Rise/Replace existing commode with new high rise commode with two (2) grab bars. Work shall include new shutoff, supply line and wax ring. Examine condition of the flange and report if damaged. Consult owner for location of grab bars. | | |
| 3 Area: BATHROOM #1 | Div.# 11.A | A 3LF | |
| Lavatory-Vanity Cabinet/Replace. Replace existing lavanity cabinet (pre-finished oak). Match existing size. | Lavatory-Vanity Cabinet/Replace. Replace existing lavatory-vanity cabinet with new vanity cabinet (pre-finished oak). Match existing size. | | |
| REPLACE 30" VANITY. | | | |
| 4 Area: BATHROOM #1 | Div.# 11.A | A 5SF | |
| Lavatory-Vanity Sinktop/Cultured Marble/Replace. Replace existing lavatory-vanity sinktop with new vanity sinktop (cultured marble). Match existing size. | Replace. Replace existing lavatory-vanity marble). Match existing size. | | |
| Print Date: Tuesday, January 22, 2019 | PO Box 578 Silwell OK 7-4960 | 60 | Dura Lata |

| Plumbing |
|--|
| 5 Area: BATHROOM #1 Div.# 11.A 1 Ea |
| Lavitory Faucet/Vanity/Install new vanity faucet, drains, supply lines & shutoffs. |
| Roofing |
| 6 Area: EXTERIOR Div.# 7.A. 30 Sq |
| |
| Drip Edge, Pipe Flashing, Valley Flashing, and Metal Slant Back Vents. |
| HOMEOWNER CHOOSE COLOR. INCLUDES ALL DRIP EDGE, VALLEY FLASHING, AND ROOF JACKS. |
| 7 Area: EXTERIOR Div.#7.C 30 Sq |
| Roofing/Strip/Asphalt-Fiberglass. Strip roof-asphalt/fiberglass. |
| All construction shall be in accordance with local codes, manufacturers' recommended |
| installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities. |



Cost Estimator/Inspector

HACN HOUSING REHAB SITE DIRECTIONS

Date

| | HARLOTTE WOL e: (918)696-424 | | | |
|---------------------------|---------------------------------|----------------------|--|--|
| Address: | PO BOX 578 STILWELL, OK | 7496 <u>0</u> | | |
| GPS Coor | dinates: <u>35.753</u> | 258,-94.646809 | | |
| Drive Time | e: <u>45 MINS.</u> | | | |
| | | | | |
| | | | | |
| | | | | |
| Dire elie e | y Franc Chanala | N. P. | | |
| stilwell. go lane)take | south on hwy5 second entran | 59 5 miles turn righ | st on hwy62/51 22 miles to not into cherry tree (duck addition on left, then right, ard. | |
| Neil Teague | 2 | | 1/18/19 | |