WorkWrite-Up and Bid Document/By Trade

	Contractor Name:			
2031 W. 25th Street N. Muskogee, OK 7-4 Con	Contractor Signature:			
	This docum	ent must be sign	This document must be signed to be a valid bid.	
PROJECT TY	PROJECT TYPE: Rehabilitation	Н	Bid Due Date:	
Trade Work Description / Comments	Gen. Spec.		Oty Unit	Item Rid
Carpentry			,	
1 Area: KITCHEN	<i>Div.</i> # 10 G	<u>.</u>	1 1 1 2	
Fire Extinguisher/Install. Install new fire extinguisher.			- 1 2	
Electrical				
2 Area: INTERIOR	<i>Div.</i> # 13.D.		5 Ea	
Smoke Detector/Battery Operated/Install new smoke detector, battery operated (10 year lithium battery). All bedrooms and hallways adjacent to bedrooms. Use Firex #4015 or written approved equal.	tector, battery operated (10 y bedrooms. Use Firex #4015 c	r		
HVAC				
3 Area: GARAGE	<i>Div.</i> # 12		ה ה	
HVAC /Central/Cooling & Propane Gas Furnace Heating 3.5 TON/13 SEER, New HVAC Equipment (13 SEER). INSIDE AND OUTSIDE EQUIPMENT/INCLUDING; New Plenum, Duct Work. Ceiling grills. Complete new installation.	g 3.5 TON/13 SEER, New HV MENT/INCLUDING; New Plen	AC	2	
lumbing				

Trade Work Description / Comments Gan Gran	O. 11	
	63	nem blu
4 Area: GARAGE Div.# 11.A	A 1 Fa	
Water Heater/ Natural Gas/40 Gallon. Replace water heater with a new 40 gal. gas water heater. Work shall include elevating to 18" (if in garage), TPR, combustion air, Gas Flex line, Flex water supply connections, and drain Pan. Code Legal Installation	Ť	
Roofing		
5 Area: ROOF Div.# 7.A.	30.Sa	
Roofing/Heritage/30 Year Warranty. Install fiberglass shingles/Minimum 30 year warranty/Use Marlarkey/Tamko or written approved equal. 30 lb Felt, Painted Style D Drip Edge, Pipe Flashing, Valley Flashing, and Metal Slant Back Vents		
6 Area: ROOF Div.# 7.A	224 SE	
Sheathing/5/8" CDX/Replace. Replace existing sheathing/Use 5/8" CDX.		
Replace all deteriorated decking		
All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement.	nended ions and Lead- be resolved by	Total:

attached Asbestos Sampling Report for location and testing of Planned Work Activities. Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See for conducting safe work practices that comply with OSHA Construction Standards for Asbestos ompliance with the more stringent requirement. Contractor awarded the job will be responsible Norma Smith site directions: Take highway 62 to Muskogee go past the Wal Mart to N. 24^{th} street W. turn right go to Hawthorne turn right go to N. 22^{nd} street W. turn right go W. 25^{th} turn left go to N. 21^{st} street West.