

WorkWrite-Up and Bid Document/By Trade

Jessica Stilwell

903 Sam Ed Bush Sallisaw, OK 7-4955
(918) 235-5274

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: Rehabilitation

Bid Due Date:

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<u>Carpentry</u>				
1	<i>Area:</i> KITCHEN Fire Extinguisher/Install. Install new fire extinguisher.	<i>Div.#</i> 10.G	1 Ea	<input style="width: 80px; height: 40px;" type="text"/>
<u>Electrical</u>				
2	<i>Area:</i> INTERIOR Smoke Detector/Battery Operated/Install new smoke detector, battery operated (10 year lithium battery). All bedrooms and hallways adjacent to bedrooms. Use Firex #4015 or written approved equal. Replace in kitchen, hallway and all bedrooms.	<i>Div.#</i> 13.D. 11	5 Ea	<input style="width: 80px; height: 40px;" type="text"/>
<u>Roofing</u>				
3	<i>Area:</i> ROOF Roofing/Heritage/30 Year Warranty. Install fiberglass shingles/Minimum 30 year warranty/Use Marlarkey/Tamko or written approved equal. 30 lb Felt, Style D Drip Edge, Pipe Flashing, Valley Flashing. Contractor is responsible for removal of all debris. Remove and replace shingles.	<i>Div.#</i> 7.A.	26 Sq	<input style="width: 80px; height: 40px;" type="text"/>

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
Roofing				
4	<i>Area: ROOF</i>	Div.# 7.A	128 SF	<input type="text"/>
Sheathing/5/8" CDX/Replace. Replace existing sheathing/Use 5/8" CDX. Replace all deteriorated decking.				

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.

Total:

Jessica Stilwell-site directions, highway 59 to Sallisaw turn left on East Redwood Street, then left at Sam Ed Bush Dr.

903 Sam Ed Bush, Sallisaw Ok. 74955

Phone #918-235-5274