



## CONSTRUCTION DOCUMENTS – ADDENDUM 02

**Date:** September 16, 2019

**Re:** Oklahoma State University  
College of Osteopathic Medicine  
at Cherokee Nation

**From:** James R Childers Architect, Inc.  
45 South 4<sup>th</sup> Street  
Fort Smith, Arkansas 72901



09-16-19

This addendum forms part of the Contract Documents, and modifies the documents as noted below. Acknowledge receipt of this addendum in the space provided on the bid form. Failure to do so may subject the bidder to disqualification.

- Item 01**      Please refer to revised drawings
- Item 02**      Please refer to revised specifications
- Item 03**      Please refer to revised DAS drawings
- Item 04**      Please refer to attached narrative

## **CONSTRUCTION DOCUMENTS – ADDENDUM 002 – 09-16-19**

### **CIVIL DRAWINGS**

### **ARCHITECTURAL DRAWINGS**

#### A1.02A

Door B006 changed to a double egress door with delayed egress controls.

#### A1.02B

Name of room B006 changed to “Cadaver Holding & Prep.”

Door B007A added delayed egress controls.

Door B003C added delayed egress controls.

Door B014B deleted.

Door B010B added.

Wall separating Gross Anatomy Prep B009 & UPS Room B012 from Basement BOH

Corridor B010 changed to 1 hour rated wall.

Door B001 changed located and became a double egress door.

#### A1.32B

Door 3000 added.

#### A1.60

Locker Room 1018 – Paper towel dispenser locations have been revised.

Locker Room 1019 – Paper towel dispenser locations have been revised.

Restroom & Dressing 2070 – Paper towel dispensers have been placed.

#### A6.00

Changes to doors: B001, B003C, B006, B007A, B010A, & B010B.

#### A7.12

09/A7.12 – Title of drawing changed.

10/A7.12 – Title of drawing changed.

#### A7.18

Interior signage to be Gemini Cast Metal - Flat Face Profile letters in Gotham Narrow font - Clear Anodized Finish.

#### A7.20

13/A7.20 – added clock to coordinate with E1.43.

#### A7.21

Detail 02 – Lobby 3000 – Doorway added, display case location revised.

#### A8.02

Restroom B023 – Wall finishes have been denoted.  
Restroom B025 – Wall finishes have been denoted.

#### A8.11

Restroom & Dressing 1057 – Wall finishes have been denoted.  
Restroom & Dressing 1058 – Wall finishes have been denoted.

#### A8.12

Locker Room 1018 – Wall finishes have been denoted.  
Locker Room 1019 – Wall finishes have been denoted.  
Corridor 1029 - Wall covering denotation has been updated.

#### A8.21

Restroom & Dressing 2069 – Wall finishes have been denoted.  
Restroom & Dressing 2070 – Wall finishes have been denoted.

#### A8.31

Restroom 3105 – Wall finishes have been denoted.  
Restroom 3109 – Wall finishes have been denoted.

#### A9.02

Ceiling in area door B001 changed per door moving, including light fixture and return grille shifting.  
Soffit in vicinity of new door B010B deleted.

#### A9.31

AP added outside Staff 8 3096 to coordinate with E1.42.

A9.32

Lobby 3000 – Doorway added, surrounding ceilings revised.

A10.00

Notes have been revised.

## **MECHANICAL DRAWINGS**

M2.00

Added fire dampers for new fire walls.

Revised return grille locations and associated ductwork for new corridor doors.

M2.11

Revised return grilles and ductwork for corridor due to door addition.

M2.14

Revised return grilles and ductwork for corridor due to door addition.

M2.15

Revised return grilles and ductwork for corridor due to door addition.

M3.00

Revised return grilles for corridor due to door addition.

M3.11

Revised return grilles for corridor due to door addition.

M3.14

Revised return grilles for corridor due to door addition.

M5.00

Revised return grilles and ductwork for corridor due to door addition.

M5.03

Revised return grilles and ductwork for corridor due to door addition.

## **ELECTRICAL DRAWINGS**

E1.05

Revised location of power for monitor in Lecture Hall 1

E1.11

Revised mounting height of TV in Student Senate Office.

E1.15

Revised location of power for monitor in Lecture Hall 2.

E1.37

Removed card reader next to Fire Pump Room where door was removed.

E1.38

Added data drop in Sim Office 1046

Revised plan to show floor boxes in OMM Lab 1060.

E1.39

Revised mounting height of clocks in Classroom LL1 and LL2. Added keynote to plan.

Revised mounting height of clock in LH1.

Revised ceiling mounted data location for monitor in LH 1.

E1.40

Revised mounting height of clocks in Exam Central Corridor. Added keynote to plan.

Added data drop in CE Office 2067.

Relocated clock in Student Lounge – Game Area.

Relocated data for podium camera.

Added keynote to phone location in CE Storage.

**E1.41**

Removed height marker next to TV in Student Senate Office.  
Added data drop Lib. Office.

**E1.42**

Added data drop in Office 5.

Added data drop in Shared Office 5.

Added data drops in RH SH Office.  
Revised mounting height of clocks in Classrooms LL3, and LL4. Added keynote to plan.

**E1.43**

Revised ceiling mounted data location in LH 2.

Revised plan to show floor box in Faculty Conference 3.

**E2.01**

Revised light fixture Q1 to correct model.

**E2.02**

Added exit light and relocated 2x2 in Basement BOH Corridor. 13.

**E2.16**

Added exit light to door added in L3 Lobby.

Removed a L1 fixture in L3 Lobby.

**SPECIFICATIONS**

1. 25505 – DIRECT DIGITAL CONTROLS
  - a. Revised “Trane” controls to be Schneider Electric with Automated Building Systems.