

Work Write-Up and Bid Document

Facilities Shop Building Shop

1300 Nola St.

Tahlequah, OK

74464-

(918) 871-9169

Contractor Name

Contractor Signature

Bid Due Date:

| Trade | Area | Description | Comments | Manual Spec | Quantity | Enter Bid |
|-------|------|-------------|----------|-------------|----------|-----------|
|-------|------|-------------|----------|-------------|----------|-----------|

Carpentry

EXTERIOR

- 1 Construct Comerical Building/ To include Build a 50 X 100 cr8 5000 ft
- finished Work inside & outside. Contractor is Red Iron Building with 14 Ft. side walls Insulated with 26 gage metal. Turn Key

- 2 Door/Exterior/Flush Faced/Pre-Hung Install 3.0 metal 8.A. 2 EA
- Steel/Replace. Replace exterior entrance door with new pre-hung steel, flush faced. walk thru doors with locks & knobs
- Work shall include paint-both sides.

- 3 Garage Vehicle Door/Repair overhead Install 2 10x12 8.C 2 EA
- garage vehicle door/See Comments. garage doors with locks

INTERIOR

Wednesday, November 20, 2019

1300 Nola St.

Tahlequah, OK

| Trade | Area | Description | Comments | Manual Spec | Quantity | Enter Bid |
|-------|------|-------------|----------|-------------|----------|-----------|
|-------|------|-------------|----------|-------------|----------|-----------|

Carpentry

INTERIOR

| | | | | | | |
|---|--|--|--------------------------------------|----|------|----------------------|
| 4 | | Door/Garage door opener. Install garage door opener. | Install door openers on garage doors | q5 | 2 ea | <input type="text"/> |
|---|--|--|--------------------------------------|----|------|----------------------|

| | | | | | | |
|---|--|---|---|------|-------|----------------------|
| 5 | | Interior Wall/Partition/2"x 4"x 10'/Replace. Replace 2" x 4" x 10' interior partition wall/16" O.C. (framing only). | Build wall across center of building floor to ceiling. With 26 gage metal on both sides | 6.C. | 50 LF | <input type="text"/> |
|---|--|---|---|------|-------|----------------------|

Concrete

EXTERIOR

| | | | | | | |
|---|--|--|--|-----|--------|----------------------|
| 6 | | Driveway Approach/Concrete/Install. Install concrete approach. | Install 2 14x20 Driveways in front of overhead doors.3500 psi concrete & Reinforcement. 4 in. Deep | 3.K | 600 SF | <input type="text"/> |
|---|--|--|--|-----|--------|----------------------|

| | | | | | | |
|---|--|---|---|------|--------|----------------------|
| 7 | | Perimeter Beam/Concrete/Replace. Replace poured concrete perimeter beam (with keyed and doweled strip footing/sized to code) foundation. Piers shall be specified separately. | Pour 2 x 3 Footing with Rebar 3500 Psi Concrete | 3.R. | 300 LF | <input type="text"/> |
|---|--|---|---|------|--------|----------------------|

| Trade | Area | Description | Comments | Manual Spec | Quantity | Enter Bid |
|-------------------|-----------------|---|--|-------------|----------|----------------------|
| <i>Concrete</i> | | | | | | |
| <i>Electrical</i> | EXTERIOR | | | | | |
| | 8 | Slab on Grade Foundation. Install new slab on grade foundation. | Pour 50 x 100 Slab 6 " Deep with Reinforcement& Vapor Barrier. 3500 Psi Concrete | 3.T. | 5000 SF | <input type="text"/> |
| | INTERIOR | | | | | |
| | 9 | Light Fixture/Repair existing light fixture/See comments. | Install Led shop lights in building | 13.D.15 | 12 EA | <input type="text"/> |
| <i>Roofing</i> | 10 | Main Service/200 Amp/Replace. Replace existing main service with new 200 Amp main service with 18 branch breakers. Work shall include replacement of weatherhead. | Install 200 amp panel box in building | 13.D.1 | 1 EA | <input type="text"/> |
| | 11 | Outlet/110v Duplex/20 Amp/Grounded/Replace 1 10 duplex outlet and cover/20 amp., grounded. | Install outlets in building 20amp every 20ft | 13.D. | 20 EA | <input type="text"/> |
| | 12 | Switch & Cover Plate/20 Amp/Replace switch and cover/20 amp. | Install light switches in building 20 amp | 13.D. | 4 EA | <input type="text"/> |

INTERIOR

Wednesday, November 20, 2019

1300 Nola St.

Tahlequah, OK

| Trade | Area | Description | Comments | Manual Spec | Quantity | Enter Bid |
|----------|------|---|--|-------------|----------|-----------|
| Roofing | | | | | | |
| INTERIOR | | | | | | |
| 13 | | Roof/Metal/R-Panel 26 Gauge/Install. Install new R-Panel metal roof (26 gauge) as per manufacturer's recommendations. | Install metal on inside of building 26 gage 8ft tall | 7.A. | 2400 S | |
| TOTAL | | | | | | |