

Work Write-Up and Bid Document/By Trade

Sharon Baty

106 N. Hazel Street Grove, OK 7-4344
 (918) 786-2792

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: Rehabilitation

Bid Due Date: _____

| Trade | Work Description / Comments | Gen. Spec. | Qty Unit | Item Bid |
|------------------------|---|-------------------|----------|----------------------|
| Carpentry | | | | |
| 1 Area: KITCHEN | Fire Extinguisher/Install. Install new fire extinguisher. | Div.# 10.G | 1 Ea | <input type="text"/> |
| Electrical | | | | |
| 2 Area: KITCHEN | Smoke Detector/Battery Operated/Install new smoke detector, battery operated (10 year lithium battery). All bedrooms and hallways adjacent to bedrooms. Use Firex #4015 or written approved equal. Install in kitchen, hallway and all bedrooms. | Div.# 13.D. 11 | 5 Ea | <input type="text"/> |
| HVAC | | | | |
| 3 Area: GARAGE | HVAC Equipment/Central/Heating & Cooling 3 Ton/13 SEER & Propane Gas Heating Replace INSIDE AND OUTSIDE EQUIPMENT/INCLUDING ; COPPER LINES, A- COIL & Coil BOX, OUTSIDE CONDENSOR; ALL VENT PIPE, Filter Grill, ceiling Registers, and new condensate line. | Div.# 12 | 1 Ea | <input type="text"/> |
| Plumbing | | | | |

| Trade | Work Description / Comments | Gen. Spec. | Qty Unit | Item Bid |
|-----------------------|--|------------|----------|----------------------|
| Plumbing | | | | |
| 4 Area: GARAGE | Water Heater/ Natural Gas/40 Gallon. Replace water heater with a new 40 gal. gas water heater. Work shall include elevating to 18" (if in garage), TPR, combustion air, Gas Flex line, Flex water supply connections, and drain Pan. Code Legal Installation. | Div.# 11.A | 1 Ea | <input type="text"/> |
| Roofing | | | | |
| 5 Area: ROOF | Roofing/Heritage/30 Year Warranty. Install fiberglass shingles/Minimum 30 year warranty/Use Marlarky/Tamko or written approved equal. 30 lb Felt, Painted Style D Drip Edge, Pipe Flashing, Valley Flashing, and Metal Slant Back Vents. Remove all debris, remove and replace all shingles. | Div.# 7.A. | 30 Sq | <input type="text"/> |
| 6 Area: ROOF | Sheathing/5/8" CDX/Replace. Replace existing sheathing/Use 5/8" CDX. Replace any deteriorated decking. | Div.# 7.A | 64 SF | <input type="text"/> |

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.

Total: