

Work Write-Up and Bid Document/By Trade

Dallis Fink

60551 E. 346 Road Grove, OK 7-4344

(818) 559-2618

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: Rehabilitation

Bid Due Date: _____

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Carpentry				
1	Area: KITCHEN Fire Extinguisher/Install. Install new fire extinguisher.	Div.# 10.G	1 Ea	<input type="checkbox"/>
Electrical				
2	Area: ENTIRE STRUCTURE Smoke Detector/Battery Operated/Install new smoke detector, battery operated (10 year lithium battery). All bedrooms and hallways adjacent to bedrooms. Use Firex #4015 or written approved equal. Install in hallway, and all bedrooms.	Div.# 13.D. 11	5 Ea	<input type="checkbox"/>
HVAC				
3	Area: GARAGE HVAC Equipment/Central/Heating & Cooling 3 Ton/13 SEER & Propane Gas Heating Replace INSIDE AND OUTSIDE EQUIPMENT/INCLUDING ; COPPER LINES, A-COIL & Coil BOX, OUTSIDE CONDENSATOR; ALL VENT PIPE, Filter Grill, ceiling Registers, and new condensate line.	Div.# 12	1 Ea	<input type="checkbox"/>
Plumbing				

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Plumbing				
4 Area: GARAGE				
	Water Heater/ Natural Gas/40 Gallon. Replace water heater with a new 40 gal. gas water heater. Work shall include elevating to 18" (if in garage), TPR, combustion air, Gas Flex line, Flex water supply connections, and drain Pan. Code Legal Installation.	Div.# 11.A	1 Ea	<input type="text"/>
Roofing				
5 Area: ROOF				
	Roofing/Heritage/30 Year Warranty. Install fiberglass shingles/Minimum 30 year warranty/Use Marlarky/Tamko or written approved equal. 30 lb Felt, Painted Style D Drip Edge, Pipe Flashing, Valley Flashing, and Metal Slant Back Vents.	Div.# 7.A.	30 Sq	<input type="text"/>
6 Area: ROOF				
	Sheathing/5/8" CDX/Replace. Replace existing sheathing/Use 5/8" CDX. Remove and replace all shingles, replace any deteriorated decking. Remove all debris from work site.	Div.# 7.A	64 SF	<input type="text"/>

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.

Total:

--