

**EXHIBIT "A"**  
**SCOPE OF WORK**

**1. Contractor's Scope of Work**

Contractor's Scope of Work shall include providing all labor, materials, and equipment to perform or provide the following:

- a. Sod cut, frame and prep the driving range tee box for a linear run of concrete located at the Cherokee Hills Golf Club, located in Catoosa, Oklahoma.
- b. Remove and dispose of all debris resulting from the demolition.
- c. Construct and install a 960 square foot of 4 inch (4") thick, 3000 psi concrete cart path, 6 feet wide by 160 feet long
- d. Repair grow-in with approved sod, including top soil on both sides of the cart path.
- e. Location of cart path will require the use of a concrete buggy or pump truck

**2. Schedule**

Contractor shall perform as follows:

- a. Strip, form and prep entire run on first day
- b. Pour concrete the following day, saw-cut when ready
- c. Commence performance on or about May 3, 2021 and complete the Work within one (1) week, weather permitting.

**3. Code of Conduct**

Contractor and the employees, agents and subcontractors of Contractor shall at all times while on the site of the Location observe the Code of Conduct for Cherokee Nation Entertainment Jobsites ("Code of Conduct"), attached hereto and incorporated herein as Exhibit " B". Any individual who fails to conduct themselves in accordance with the Code of Conduct will be removed from the Location and will not be allowed to return without written authorization from an authorized Company Representative.



NORTH

