

SCOPE OF WORK

WORK WILL ENCOMPASS THE REMOVAL AND REPLACEMENT OF THE CLEAR SKYLIGHT COVERING OF THE CANOPIES LEADING FROM THE SKYWALK ENTRY TO LOT "1" WITH 26GA. "BURNISHED SLATE" R-PANEL AND REINFORCED AT THE EXTERIOR PERIMETER WITH 2" X 2" SQUARE TUBING.

- **PROJECT WILL INCLUDE LABOR, EQUIPMENT, AND MATERIALS NEEDED TO REPLACE THE CANOPY COVERINGS AS NOTED ABOVE.**
- **BID MUST BE ITEMIZED.**
- **CONTRACTOR WILL BE RESPONSIBLE FOR TAKING OWN MEASUREMENTS FOR PURPOSE OF BID.**
- **WORK WILL INCLUDE THE REMOVAL, CLEANUP AND DISPOSAL OF THE EXISTING COVERING AND ANY SCRAP OR BYPRODUCT FROM THE REINSTALLATION PROCESS.**
- **CONTRACTOR WILL BE RESPONSIBLE FOR SAFETY BARRICADES AND SITE MANAGEMENT OF THE WORK AREA DURING THE INSTALLATION/REMOVAL WORK.**
- **ALL WORK WILL BE PERFORMED IN COMPLIANCE WITH LOCAL, STATE, AND CHEROKEE SAFETY AND OSHA REGULATIONS AND PROCEDURES.**