

WorkWrite-Up and Bid Document/By Trade

Edna Prewitt {Plumbing}
407 Sequoyah Ave. Vinita, OK 7-4301
(539) 323-0401

Contractor Name:

Contractor Signature:

This document must be signed to be a valid bid.

PROJECT TYPE: Emergency Repairs

Bid Due Date:

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
Plumbing				
1 Area: PLUMBING		Div.# 11.A.	66 LF	
	Yard Line/Sewer/PVC. Replace sewer line in yard with PVC to include double cleanout.			
	Replace the drain line from the house to the city sewer line. Use 3" or 4" Pipe which ever the city requires. Check in with the Vinita City Code Inspectors for required permits.			
	Grade and rake ditch areas smooth at completion.			

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement.

Total:

HACN HOUSING REHAB SITE DIRECTIONS

Name: Edna Prewitt

Telephone: (918)323-0565

Address: 407 W. Sequoyah Ave
Vinita, OK 74301

County: Craig

Year Built: 1970

GPS Coordinates: 36.64337,-95.15713 **Drive Time:** 1 hr From Tahlequah,ok.



Directions: From Cherokee Nation, Hwy 82 North to Locust Grove, then Hwy 412 to the Chouteau exit, then Hwy 69 North toward Pryor, Ok continue on hwy 69 for 30 miles to jct. 69 & 60 then, turn right onto 69 hwy go to Vinita and go to Sequoyah Ave and turn left & go 3-blocks to 407 Seq ave on the left.

Mike Dreadfulwater
Cost Estimator/Inspector

7/18/22
Date