

# WorkWrite-Up and Bid Document/By Trade

**Rebecca Martin**

Contractor Name:

5753 E 590 Rd Locust Grove, OK 7-4352  
 (918) 479-2710

Contractor Signature:

This document must be signed to be a valid bid.

**PROJECT TYPE: Rehabilitation**

**Bid Due Date:**

Trade	Work Description / Comments	Gen. Spec.	Qty Unit	Item Bid
<b>Carpentry</b>				
<b>1</b>	<b>Area: BATHROOM #1</b> Base Trim/Pine, K- Pattern 2-1/4" Solid/ Stain Grade /Replace. Replace base trim, K- Trim, solid pine, 2-1/4". Stain & Finish. <span style="color: red;">Replace trim. Paint included.</span>	Div.# 6.N	40 LF	<input type="text"/>
<b>Drywall &amp; Finish</b>				
<b>2</b>	<b>Area: BATHROOM #1</b> Drywall/Moisture Resistant/Replace. Replace existing drywall with new moisture resistant drywall- 1/2". Interior Drywall or written approved equal. <span style="color: red;">Install greenrock as needed. Tape &amp; texture.</span>	Div.# 9.D	30 SF	<input type="text"/>
<b>Flooring</b>				
<b>3</b>	<b>Area: BATHROOM #1</b> Vinyl Floor Tile. Replace existing flooring with glue down vinyl tile floor tile. 5 mil <span style="color: red;">Remove vct &amp; install vinyl planks.</span>	Div.# 9.L	75 SF	<input type="text"/>
<b>Paint &amp; Finish</b>				

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
<b>Paint &amp; Finish</b>				
4	<i>Area:</i> BATHROOM #1 Paint Bathroom /Ceilings, Walls, & Trim /Paint Two coats, . Work shall include minor repairs to surfaces. SF=ACTUAL SURFACE AREA OF WALLS & CEILING. <i>Paint bathroom.</i>	Div.# 9.N.3	400 SF	<input type="text"/>
<b>Plumbing</b>				
5	<i>Area:</i> BATHROOM #1 Commode/High Rise/Handicap /Replace commode with new high rise/Handicap commode with two (2) grab bars. include new shutoff, supply line and wax ring. Examine condition of the flange and report if damaged. Consult owner for location of grab bars. <i>Install HC toilet.</i>	Div.# 16.C.	1 Ea	<input type="text"/>
6	<i>Area:</i> BATHROOM #1 Shower/Handicap/Pre-Fab/Install Shower kit and drain, with 3-grab bars, fold down shower seat, and pressure balanced shower valve with glide bar, and shower head. <i>Install HC shower. Use Locke #A1117. Include removable shower seat and hand held shower head.</i>	Div.# 16.C.	1 Ea	<input type="text"/>
<b>Site Work</b>				
7	<i>Area:</i> INTERIOR Cleanup/Final. Final cleanup of entire Project. <i>Remove all trash &amp; debris.</i>	Div.#	1 SF	<input type="text"/>

Trade

Work Description / Comments

Gen. Spec.

Qty Unit

Item Bid

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement. Contractor awarded the job will be responsible for conducting safe work practices that comply with OSHA Construction Standards for Asbestos Workers. Asbestos report, where required, will be attached if areas tested are 1% or greater. See attached Asbestos Sampling Report for location and testing of Planned Work Activities.

Total: