

WorkWrite-Up and Bid Document/By Trade

Beverly Wimberly (Roof)
 607 Wilson St Sallisaw, OK 7-4955
 (318) 393-8468

Contractor Name: _____

Contractor Signature: _____

This document must be signed to be a valid bid.

PROJECT TYPE: Emergency Repairs

Bid Due Date:

<i>Trade</i>	<i>Work Description / Comments</i>	<i>Gen. Spec.</i>	<i>Qty Unit</i>	<i>Item Bid</i>
Roofing				
1 Area: ROOF				
	Roofing/Heritage/30 Year Warranty. Install fiberglass shingles/Minimum 30 year warranty/Use Marlarky/Tamko or written approved equal. 30 lb Felt, Painted Style D Drip Edge, Pipe Flashing, Valley Flashing, and Metal Slant Back Vents.	Div.# 7.A.	28 Sq	
2 Area: ROOF				
	Roofing/Strip/Asphalt-Fiberglass. Remove all layers, and haul roofing debris to a Legal Waste Dump for disposal.	Div.# 7.C	28 Sq	
	Remove all layers including felt.			

All construction shall be in accordance with local codes, manufacturers' recommended installation procedures, good quality workmanship practices, General Specifications and Lead-Based Paint requirements when applicable. Conflicts between requirements will be resolved by compliance with the more stringent requirement.

Total:



HACN HOUSING REHAB SITE DIRECTIONS

Name: Beverly Wimberly

Telephone: (318)393-8468

Address: 607 Wilson St
Sallisaw, OK 74955

County: Sequoyah **Year Built:** 1970

GPS Coordinates: 35.46486, -94.78048 **Drive Time:** 56 Mins



Directions: From Cherokee Nation, Turn right onto US-62 E and go .7 miles to Hwy 82 S, turn right onto Hwy 82 S and go 23.2 miles to Hwy 82 S, turn left onto Hwy 82 S and go 8.4 miles to US 62 E, turn left onto US 62 E and go 12.1 miles to J T Stites Bullevard, turn left onto J T Stites Bullevard and go .1 miles to W Redwood Ave, turn right onto W Redwood Ave and go 1.9 miles to Sam Ed Bush Dr, turn left onto Sam Ed Bush Dr and go .1 miles to Wilson St, turn right onto Wilson st, home will be first house on right

Scotty Woodard
Cost Estimator/Inspector

4/17/23
Date