

Will Rogers MDF Building Questions

1. Confirm no prevailing wage rates apply to this project. **No prevailing wages**
2. What is the scope of work requested related to the existing fire riser and suppression equipment in the existing building? **Contractor will need to remove the fire suppression components, compressor, heater, etc. and leave them on site. Demo and cap underground piping at closest joint, flag location above ground.**
3. Please provide footing details (size, depth, reinforcement) as well as CMU wall reinforcement details, ceiling details. Plans call for hard lid on 2x8 joists but concrete lid was discussed at pre-bid. **Please price concrete lid as Alternate #3**
4. Will there be any attic insulation? **See revised drawing notes**
5. Is the outdoor run area (102) to be concrete slab? **No, dirt only**
6. Confirm exterior siding (Hardie or plywood) is to be painted. **See revised drawing notes**
7. What is the proposed finished floor elevation of the building? **See revised drawing notes**
8. Can conduits and devices inside CMU room 100 be surface mounted? **Yes**