CHEROKEE NATION Environmental Programs



Asbestos Sampling Report

PARTICIPANT: HUNTER, LARRY

PREPARED BY: / Clark

DATE: 9-19-19

NICK CLARK, ENVIRONMENTAL SPECIALIST III

REQUESTED BY: HACH HOUSING REHABILITATION - GEORGE HUBBARD

TABLE OF CONTENTS

- I. SITE INSPECTION/DESCRIPTION
- II. BACKGROUND
- III. FIELD PROCEDURES AND ANALYTICAL METHODS
- IV. SUMMARY OF FINDINGS
- V. CONCLUSIONS

APPENDIX A: PROJECT SCOPE OF WORK

APPENDIX B: LABORATORY REPORT & CHAIN OF CUSTODY

APPENDIX C. SITE PHOTOGRAPHS

I. Site Inspection/Description

Cherokee Nation Environmental Programs (CNEP) has conducted asbestos sampling for the presence of asbestos containing materials (ACM) for the following site:

Site Name: Larry Hunter Address: 473092 E. 770 Rd. Stilwell, OK 74960 Phone 918-507-3011 Lat/Long

The sampling was performed to determine the presence of all ACM from within the affected parts of the structure for EPA's National Emissions of Hazardous Air Pollutants (NESHAP) compliance as well as OSHA worker protection.

The inspector responsible for this project was:

Nick Clark ODOL, AHERA Inspector, License No: OK401243

The sampling was conducted on September 12, 2019 at the request of the Cherokee Nation Housing Rehabilitation Department.

The site is a single family home built in 1978. Sampling was limited to areas that would be affected by the project scope of work (Appendix A) provided by the housing rehabilitation department.

ACM was found at this site. See Section IV for locations.

II. BACKGROUND

The Oklahoma Department of Environmental Quality (ODEQ) has adopted EPA's NESHAP regulation under OAC252:100, 41-15 and has been delegated authority in the state of Oklahoma for its enforcement. Section 61.145(a) of Federal EPA regulation states that prior to commencement of the demolition or renovation of a facility a thorough inspection of the affected part or parts of a facility is required to determine the presence of all asbestos including Category I and Category II non-friable, and friable ACM. ACM is defined by EPA and OSHA as any material that contains greater than 1% asbestos.

III. FIELD PROCEDURES AND ANALYTICAL METHODS

During the on-site inspection, we visually assessed the physical characteristics of suspect asbestos-containing materials (SACM) based on homogeneous areas. Homogeneous areas are areas of asbestos similar in color, texture, and construction, date of application, and in general appearance. For purposes of renovation and demolition, homogeneous areas of SACM can be further classified according to NESHAPs rules by whether the material is friable, Category I non-friable, or Category II non-friable.

<u>Friable ACM</u> is defined by NESHAPs rules as any material containing more than 1% asbestos as determined by Polarized Light Microscopy (PLM), that, when dry, can be crumbled, pulverized or reduced to powder by hand pressure.

<u>Category I Non-friable ACM</u> is defined by NESHAPs rules as any asbestos-containing packings, gaskets, construction mastics, resilient floor covering (i.e. floor tiles, roll sheet flooring) or asphalt roofing products that contain more than 1% asbestos as determined by PLM.

Category II Non-friable ACM is defined by NESHAPs rules as any material, excluding Category I non-friable ACM, containing more than 1% asbestos as determined by PLM, when dry, cannot be crumbled, pulverized, or reduced to powder by hand pressure.

Typically, non-friable materials, such as transite (cementious products) and vinyl floor tiles are not regulated by the State of Oklahoma provided they do not become friable. General deterioration, machine grinding, drilling, sanding, and dry-buffing are all ways of causing non-friable materials to become classified as Regulated Asbestos Containing Materials (RACM). All friable materials are classified RACM. Please note that the following materials, even though classified as non-friable are fully regulated by Oklahoma Department of Labor for removal purposes as friable material: ceiling tiles, roll sheet flooring (linoleum), and joint wall compound when deemed friable

In addition to classification of suspect material into friable and non-friable materials, a determination of current condition was conducted as part of the physical assessment. The condition noted is the representative of the material at the time of inspection. Conditions of materials can change very quickly when disturbed. All suspect material was placed in one of the following categories of condition.

Significantly damaged: Material that is damaged, blistered, deteriorated, water stained over at least 10% of its total area.

<u>Damaged</u>: Material that is damaged, blistered, deteriorated, water stained less than 10% of its total area.

Good: Material that has no visible damage or deterioration.

Guidelines used for the number of samples collected per homogeneous area were determined using the Asbestos Hazard Emergency Response Act (AHERA) protocol promulgated in 40 CFR 763, Appendix E as follows:

Surfacing materials - material that is sprayed or troweled on wall, ceilings, or support columns for fireproofing, acoustical, or even decorative purpose.

- Less than 1000 ft2 Minimum 3 samples
- From 1000-5000 ft2 Minimum 5 samples
- Greater than 5000 ft2 Minimum 7 samples

Thermal System Insulation(TSI) materials – thermal system insulation material applied to tanks, boiler, pipes or other structural component for an insulating purpose.

- May omit areas of fibrous glass, foam glass, rubber, and Styrofoam form sampling.
 Areas that have mastic on seams or outer jacketing will be sampled.
- · At least three samples must be collected from each homogeneous area of TSL
- · Plus an additional sample from each patched area of less than 6 linear feet.
- Fittings require a sufficient amount to determine positive or negative nature.
- Inspector will first collect samples from damaged areas, exposed ends, or areas missing jacketing first.

Miscellaneous materials – all other material that are not thermal system insulation or surfacing materials. This includes gaskets, packings, joint wall compound, cementious asbestos materials, ceiling tiles resilient flooring materials, construction mastics, etc..

- May assume and document as such
- A sufficient amount of samples to determine negative or positive nature. A minimum
 or one per suspect homogeneous area.
- · Collect samples from inconspicuous locations.
- Material such as cementious asbestos or vibration dampening cloths should not be sampled and will be assumed ACM unless instructed by client to collect these samples.

Bulk samples of suspect ACM were analyzed by Polarized Light Microscopy (PLM) in accordance with EPA Methods 600R-93/116. All samples were sent to a NVLAP accredited laboratory for analysis. Quantem laboratories (NVLAP # 101959-0) in Oklahoma City, OK analyzed the samples. A copy of the full laboratory report and chain of custody can be found in Appendix B.

IV. SUMMARY OF FINDINGS

A total of 3 samples were analyzed from 1 homogeneous areas due to multi-layers of material within some homogeneous sample areas. Photographs of all ACM can be found in Appendix C. All accessible and observable areas within the renovation area were sampled for ACM. Samples were not taken of suspect materials that may have placed the inspector at risk of injury (i.e. electrical panel boxes).

Any suspect ACM that have not been tested and/or found positive for asbestos must be assumed ACM until they are analyzed. Upon review of laboratory analysis, the following asbestos containing materials can be found in Table 1. All suspect ACM samples that were analyzed and did not contain asbestos can be found in Table 2.

Sample #	Material Description	Locations	Friability (Friable, NF Cat I NF Cat II)	Condition	Sample Results (% Asbestos)
01-01 01-02	Drywall Texture	Closet Under Stairs	Friable	Good	3
01-03					

Table 2. N	on – Asbestos Containing Ma	terials		
Sample #	Material Description	Locations	Condition	Sample Results (% Asbestos)
· · · · · · · · · · · · · · · · · · ·	and the second s	The first own of the transfer of the State o		And the second s

V. CONCLUSIONS

Asbestos is not always an immediate hazard. Intact and undisturbed ACM does not pose a health risk. They may, however become a health hazard if they are damaged, disturbed, or deteriorate over time and release fibers into the air. There are no federal, state, or Tribal laws mandating asbestos removal. It is only when the material can no longer be maintained in good condition and/or airborne concentrations of asbestos are measured and found to be above a permissible exposure limit (PEL), or when the building is to be demolished or renovated, that removal may become necessary. Any renovation/demolition work which may impact these positive materials should be conducted in accordance with all applicable Federal, state, and local regulations.

APPENDIX B.

LABORATORY RESULTS &
CHAIN OF CUSTODY



2033 HERITAGE PARK DR, OKLAHOMA CITY, OK 73120

1.800.822.1650

Polarized Light Microscopy Asbestos Analysis Report

QuanTEM Lab No. 314602

Account Number:

C162

Date Received:

09/16/2019

Received By:

Elena LaFarge

Date Analyzed: Analyzed By:

Methodology:

09/18/2019

Cassie Sanborn

EPA/600/R-93/116

Client: Cherokee Nation Environmental Programs

Carlton N Clark

PO Box 948

Tahlequah, OK 74464

Project: Larry Hunter

Project Location: Stilwell

Project Number: N/A

QuanTEM Sample ID	Client Sample ID	Composition	Color / Description	Asbestos (%)		Non-Asbestos Fiber (%)	Non Fibrous
001	01-01	Layered	White Texture	Asbestos Present Chrysotile	3	NA	CaCO3 Paint
001a		Layered	White Joint Compound	Asbestos Present Chrysotile	3	NA	CaCO3
002	01-02	Layered	White Texture	Asbestos Present Chrysotile	3	NA	CaCO3 Paint
002a		Layered	White Joint Compound	Asbestos Present Chrysotile	3	NA	CaCO3
003	01-03	Layered	White Texture	Asbestos Present Chrysotile	3	NA	CaCO3 Paint
003a		Layered	White Joint Compound	Asbestos Present Chrysotile	3	NA	CaCO3
003b		Layered	White Sheetrock	Asbestos Not Present		Cellulose 1	5 Gypsum

Unless otherwise noted, upon receipt the condition of the sample was acceptable for analysis.

QuanTEM is a NVLAP accredited PLM laboratory (Lab Code: 101959-0). This report relates only to the specific items tested. NVLAP accreditation applies only to analysis performed utilizing EPA/600/M4-82-020 and EPA/600/R-93/116 methods. This report may not be used to claim product endorsement by NVLAP or any agency of the US Government. This report may not be reproduced except in full, without the written approval of the laboratory.



2033 HERITAGE PARK DR, OKLAHOMA CITY, OK 73120

1.800.822.1650

Carlton N Clark PO Box 948

Tahlequah, OK 74464

Polarized Light Microscopy Asbestos Analysis Report

QuanTEM Lab No. 314602

Account Number:

C162

Date Received:

09/16/2019

Received By:

Elena LaFarge

Date Analyzed:

09/18/2019

Analyzed By: Methodology:

QuanTEM

Sample ID

EPA/600/R-93/116

Cassie Sanborn

Client

Sample ID

Composition

Color /

Description

Project: Larry Hunter

Project Location: Stilwell

Project Number: N/A

Non Fibrous

Non-Asbestos Fiber (%)

Client: Cherokee Nation Environmental Programs

Cassie Sanbor

Cassie Sanborn, Analyst

9/18/2019

Asbestos (%)

Date of Report



ASBESTOS CHAIN OF CUSTODY

Page 1 of 1

Lab No.

2033 Heritage Park Drive, Oklahoma City, OK 73120-7502 (800) 822-1650 • (405) 755-7272 • Fax: (405) 755-2058

0) 822-1650 • (405) 755-7272 • Fax: (405) 755-2058

-
00
-
2.77
LL.
-
100
-
-
- Charles
00
Lake
0
2 312
ш
IA
ш
-
and the
1
ш
-
-
-
U
-
-
-
_
-
15
-
ш
-

Cooperate Controlled Nation Environmental Programs Received Nation Environmental Programs Received Nation Environmental Programs Received Nation Environmental Programs (ed. 19.13 15-7451) Project Learner Still Mell Indicated Nation Environmental Programs (ed. 19.12 17.24 2.25.24.2.) Controlled Clark Cont	Company		- dironme						-			TEAM Woheite
Control C. Nicolas Clark Control C. Nicolas				ental Programs	Phone:	453-5000		Larry Hun	ter		צ	חמווו דוגו גגבראווב
Sample Bro Name C. Nicolas Clark Cone. 9/12/19 Date & TIME Date &	Contact:	C. Nicolas Clark			Cell Phone: (918);	316-7451	Project Location:	Stilwell				nail cartton-dark@cherokee.
Name of the control	Account #	c162			E-mail: carlton-clark(@cherokee.org	Project ID:				0	ther
C	SAMPLE	D BY: Name: C. Nicola	s Clar	Y			P.O. Number:	225542				
C		RELINQUISH	ED BY		DATE & TIME		VIA		RECEIVI	ED BY		DATE & TIME
PLM PLM TEM TEM	1	Sill ?	1		9-12-6 3pm	15	Lit	0	inal	pople	1	6111116
FILM					0	- 4		\$	0	1 01		9. Dam
FPLM					REQUESTED SE	RVICES (Ple	ase 🗹 the Ap	propriate	Boxes)			
		PLM		PLM		TEN	V		TEI	M		URNAROUND TIM
Control out of the count of the c		ilk Analysis (EPA 600/R-93/116		Vermiculite Attic In:	sulation	Air-AHERA		Bulk	Presence / Absence	EPA600/R-93/116		☐ Rush
□ 1000 Point Count □ 1000	\$	O Point Count		(EPA 600/R-04/004)		Air-NIOSH 740	2	ž	- Quantitative (weigh	196]- Chatfield	Ш	Same Day
□ Gravimento Pequantion PCAM □ Inhiking Water- EPA 100.2 □ Dinking Water- EPA 1	02	100 Point Count		Ouiei		Air-ISO 10312		Dust	- Presence / Absence	ă.		24 - Hour
No. Sample ID (and case) III NOSH 7400 Wolume 1 Per 6004-83-043 III Other Order Comments / Notes 1 01-01 III OChaarces Maxy Analyzed Analyzed Color Comments / Notes 2 01-01 III White Drywall Texture Closet under stairs 3 01-03 III White Drywall Texture Closet under stairs 4 III White Drywall Texture Closet under stairs 5 III White Drywall Texture Closet under stairs 6 III White III White III White 7 III White III White III White 8 III White III White III White	3	avimetric Preparation		PCM		Drinking Water	EPA 100.2	Dust	- Quantitative [fibers	s/sq.cm]- ASTM D5755		
No. Sample ID (do Characters Max) Analyzed Analyzed Color Color (as applicable) Comments / Notes 1 01-01 ✓ White Drywall Texture closet under stairs 2 01-02 ✓ White Drywall Texture closet under stairs 3 01-03 ✓ White Drywall Texture closet under stairs 5 Image: Color of the color of th	E .	rticle ID		NIOSH 7400		Waste Water- E	PA 600/4-83-043	of state	a.			5-Day
1 01-01 ☑ White Drywall Texture closet under stairs 2 01-02 ☑ White Drywall Texture closet under stairs 4 ☐ White Drywall Texture closet under stairs 5 ☐ Closet under stairs closet under stairs 6 ☐ Closet under stairs closet under stairs 7 ☐ Closet under stairs 8 ☐ Closet under stairs 9 ☐ Closet under stairs 10 ☐ Closet under stairs	No.		To Be	Color		Descrip	otion		Volume / Area (as applicable)	Com	ments	/ Notes
2 01-02 ✓ White Drywall Texture closet under stairs 4 O1-03 ✓ White Drywall Texture closet under stairs 5 O1-03 O1-03 O1-03 Closet under stairs 6 O1-03	-	01-01	$\overline{\Sigma}$	White		Drywall T	exture			close	t unde	r stairs
3 01-03 ✓ White Drywall Texture closet under stairs 4 ✓ Closet under stairs 5 ✓ Closet under stairs 6 ✓ Closet under stairs 7 Closet under stairs 8 Closet under stairs 9 Closet under stairs 9 Closet under stairs 10 Closet under stairs	2	01-02	2	White		Drywall T	exture			close	t unde	r stairs
5 6 6 7 7 8 8 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9 9	m	01-03	2	White		Drywall T	extrue			elose	t unde	r stairs
5 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6 6	4											
6 7 8 9 10	S											
7 8 9 10	9											
9 01	~											
01	00											
01	6											
	10											

APPENDIX C. SITE PHOTOGRAPHS

NO PHOTOS WERE TAKEN DURING THIS INSPECTION CONTACT ME IMMEDIATELY IF NEEDED